

6/20/2008 10:59:01 AM

F:\000000\Chicago - CAD\Drawings\04 - Summary\02.dgn

F.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	00-00043-00-BR	FORD	51	4
FED. ROAD DIST. NO. 3	ILLINOIS	CONTRACT NO. 87198		

(1) (2) (3)  
X120-5B X120-5B X120-5B

(1) (2) (3)  
X120-5B X120-5B X120-5B

HOLMES ST.  
PINE ST.  
CENTER ST.

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	HOLMES STREET	PINE STREET	CENTER STREET
56400100	* FIRE HYDRANTS TO BE MOVED	EACH	1	1		
58700300	CONCRETE SEALER	SQ FT	570	570		
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	4	1		3
60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2			2
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2			2
60266900	VALVE BOXES TO BE MOVED	EACH	1	1		
60266910	VALVE BOXES TO BE REMOVED	EACH	2			2
60500205	FILLING CATCH BASINS	EACH	2			2
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6,24	FOOT	593	536		57
63000000	* STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	50	50		
63000005	* STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	100		50	50
63100041	* TRAFFIC BARRIER TERMINAL, TYPE 1B	EACH	2	2		
63100045	* TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2		
63100105	* TRAFFIC BARRIER TERMINAL, TYPE 10	EACH	4	4		
66900200	* NON-SPECIAL WASTE DISPOSAL	CU YD	500	250	250	
66900450	* SPECIAL WASTE PLANS AND REPORT	L SUM	1	0.34	0.33	0.33
66900510	* BETX-PNAS SOIL ANALYSIS	EACH	3		3	
66900530	* SOIL DISPOSAL ANALYSIS	EACH	3	1	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	6	1	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	0.8	0.1	0.1
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	250	150		100
72000100	SIGN PANEL - TYPE 1	SQ FT	81	19	31	31
72500100	OBJECT MARKER - TYPE 1	EACH	4		2	2
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	10	10		
73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	1	1		
78000200	* THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	774	694	80	
78000650	* THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	62	62		
80400100	* ELECTRIC SERVICE INSTALLATION	EACH	1	1		
81000500	* CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL	FOOT	85	85		
81200220	* CONDUIT EMBEDDED IN STRUCTURE 1 1/2" DIA., PVC	FOOT	353	353		

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	HOLMES STREET	PINE STREET	CENTER STREET
81300320	* JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 8"x8"x6"	EACH	8	8		
81300980	* JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 8"x8"x6"	EACH	4	4		
81400100	* HANDHOLE	EACH	2	2		
81702100	* ELECTRIC CABLE IN CONDUIT, 600 V (XLP-TYPE USE) 1/C NO. 12	FOOT	440	440		
81702120	* ELECTRIC CABLE IN CONDUIT, 600 V (XLP-TYPE USE) 1/C NO. 8	FOOT	920	920		
82500505	* LIGHTING CONTROLLER, SPECIAL	EACH	1	1		
84200500	* REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	8		4	4
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	436	436		
X0325241	TEMPORARY PAVEMENT 11"	SQ YD	204	204		
XX003067	CONCRETE BRIDGE RAIL (SPECIAL)	FOOT	316	316		
XX006697	* LUMINAIRE (SPECIAL)	EACH	4	4		
Z0002750	BARRICADE, TYPE III	EACH	6	2	2	2
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1		
Z0038700	PERMANENT BENCH MARKS	EACH	1	1		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
Z0062450	SAWING PAVEMENT (FULL DEPTH)	FOOT	505	361	74	70
Z0067400	STEEL CASING 14"	FOOT	50			50
	* REINFORCED CONCRETE LIGHT POLES (SPECIAL)	EACH	4	4		
	* CONDUIT ATTACHED TO STRUCTURE (SPECIAL)	FOOT	8	8		
67100100	MORTALIZATION	L SUM	1	1		
Z0076600	Δ TRAINEES	HOURL	500	500		

\* SPECIALTY ITEMS  
Δ 1080

**SUMMARY OF QUANTITIES**

HOLMES STREET OVER  
ILLINOIS CENTRAL RAILROAD  
CITY OF PAXTON, FORD COUNTY

DESIGN BY KLA	DRAWING NO. C-4	Job# C-93-016-01
DRAWN BY DJR		DATE 7/1/08
CHECKED BY JAH		SCALE AS SHOWN



DATE REVISIONS