EARTH EXCAVATION	
STA. TO STA.	CU. YD.
60+52 TO 61+50 LT	7
60+57 TO 61+50 RT	7
TOTAL	14

TEMPORARY RAMP	
LOCATION	SQ. YD.
STA. 54+65	64
TOTAL	64

AGGREGATE SHOULDERS, TY B	
STA. TO STA.	TONS
54+65 TO 61+50	87
TOTAL	87

HMA SHOULDERS, 8"	
STA. TO STA.	SQ. YD.
60+52 TO 61+50 LT	33
60+57 TO 61+50 RT	31
TOTAL	64

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE		
STA. TO STA.	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)
54+65 TO 61+50	51	51
TOTALS	51	51

MOWING	
STA. TO STA.	UNIT
54+65 TO 61+50	7
TOTAL	7

DETECTOR LOOP, TYPE 1	
LOCATION	FOOT
STA. 57+41 LT	144
TOTAL	144

PAVEMENT MARKING SCHEDULE							
STA. TO STA.	SHORT-TERM PAVEMENT MARKING (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS (SQ FT)	THERMOPLASTIC PAVEMENT MARKING -LINE 4" (FOOT)	PREFORMED PLASTIC PAVEMENT MARKING, TY B -LINE 6" (FOOT)	THERMOPLASTIC PAVEMENT MARKING -LINE 8" (FOOT)	THERMOPLASTIC PAVEMENT MARKING -LINE 12" (FOOT)
54+65 TO 61+50	708	236	32	3066	360	59	54
TOTALS	708	236	32	3066	360	59	54

TABULATION OF RESURFACING QUANTITIES											
LOCATION	PAVEMENT AREA	SHOULDER AREA	HMA SURF REM - BUTT JOINT	HMA SURF REM, 2"	HMA SURF REM, VAR DEPTH	HMA SURF REM, 3/4"	BIT MTRLS (PRIME COAT)	AGG (PRIME COAT)	POLY LEV BNDR (MM), IL-4.75, N50	POLY HMA SURF CSE, MIX "D", N70	HMA SHOULDERS
(STA. TO STA.)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(TON)	(TON)	(TON)	(TON)	(TON)
54+65 TO 54+95	224	23	248				0.1	0.7	9.4	18.9	2.9
54+95 TO 59+87	3028	379		3407			1.7	9.8	127.2	254.4	47.7
59+87 TO 60+12	185	17			202		0.1	0.6	7.8	15.5	2.1
60+12 TO 61+50	1034	28				1062	0.5	3.2	43.4	86.8	3.6
TOTALS	4471	447	248	3407	202	1062	3	14	188	376	56

APPLICATION RATES USED TO CALCULATE PLAN QUANTITIES FROM STA. 54+65 TO STA. 61+50

ITEM	APPLICATION RATE
BITUMINOUS MATERIALS (PRIME COAT)	0.0004 TON / SQ. YD. (ON MILLED SURFACE) 0.00012 TON / SQ. YD. (ON NEW BINDER)
AGGREGATE (PRIME COAT)	0.002 TON / SQ. YD. (ON MILLED SURFACE) 0.001 TON / SQ. YD. (ON NEW BINDER)
HMA SURFACE, LEVELING BINDER, AND SHOULDERS	112 LBS. / SQ. YD. PER INCH OF THICKNESS
AGGREGATE SHOULDERS	2.05 TON / CU. YD.

• (10,12)RS-6;11RS-4;(10B)BR