

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	*	PEORIA	186	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	IL RTE 29	
* (10,12)RS-6;11RS-4;(110)BR				

SUMMARY OF EARTHWORK					
LOCATION	EARTH EXCAVATION	CUT * 0.7	EMBANKMENT	WASTE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD	CU YD
RELO. TR 103 - STAGE I	1903.0	1332.1	1282.0	50.10	50.10
RELO. TR 103 - STAGE II	687.0	480.9	35.0	445.90	496.00
TEMP ENTRANCE	1094.0	765.8	59.0	706.80	1202.80
IL 29	1934.0	1353.8	1614	(260.20)	942.60
TR 103 W	103.0	72.1	16.0	56.10	998.70
TR 103 B	216.0	151.2	13.0	138.20	1136.90
DRAINAGE DITCH	575.0	402.5	0	402.50	1539.40
TOTAL	6512	4558	3019	1539	1539

SUMMARY OF EARTHWORK - TR 103 W					
LOCATION	EARTH EXCAVATION	CUT * 0.7	EMBANKMENT	WASTE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD	CU YD
STA 8+50 TO 9+50	103.0	72.1	16	56.10	56.10
TOTAL	103	72	16	56	56

SUMMARY OF EARTHWORK - RELOCATED TR 103 - STAGE I					
LOCATION	EARTH EXCAVATION	CUT * 0.7	EMBANKMENT	WASTE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD	CU YD
STA 20+00 TO 31+50	1359.0	951.3	924	27.30	27.30
STA 31+50 TO 37+50	544.0	380.8	358	22.80	50.10
TOTAL	1903	1332	1282	50	50

SUMMARY OF EARTHWORK - TR 103B					
LOCATION	EARTH EXCAVATION	CUT * 0.7	EMBANKMENT	WASTE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD	CU YD
STA 11+00 TO 12+19	216.0	151.2	13	138.20	138.20
TOTAL	216	151	13	138	138

SUMMARY OF EARTHWORK - RELOCATED TR 103 - STAGE II					
LOCATION	EARTH EXCAVATION	CUT * 0.7	EMBANKMENT	WASTE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD	CU YD
STA 35+72.97 TO 37+50	687.0	480.9	35	445.90	445.90
TOTAL	687	481	35	446	446

SUMMARY OF EARTHWORK - DRAINAGE DITCH					
LOCATION	EARTH EXCAVATION	CUT * 0.7	EMBANKMENT	WASTE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD	CU YD
STA 121+50 TO 125+00	575.0	402.5	0	402.50	402.50
TOTAL	575	403	0	403	403

SUMMARY OF EARTHWORK - TEMPORARY ENTRANCE					
LOCATION	EARTH EXCAVATION	CUT * 0.7	EMBANKMENT	WASTE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD	CU YD
STA 51+67 TO STA 55+01.47	1094.0	765.8	59	706.80	706.80
TOTAL	1094	766	59	707	707

CONCRETE REMOVAL SCHEDULE	
STATION	CONCRETE REMOVAL CU YD
STA 84+60 RT	3
TOTAL	3

PAVEMENT REMOVAL SCHEDULE		
STATION	PAVEMENT REMOVAL LENGTH FT	PAVEMENT REMOVAL SQ YD
STA 79+95.50 TO STA 80+43	47.5	432.78
STA 80+96.50 TO STA 81+43.50	47	428.22
TOTAL		861

SUMMARY OF EARTHWORK - IL 29					
LOCATION	EARTH EXCAVATION	CUT * 0.7	EMBANKMENT	WASTE (BORROW)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD	CU YD
STA 62+57.24 TO 73+00	707.0	494.9	161	333.90	333.90
STA 73+00 TO 80+31.5	434.1	303.9	440.1	(136.23)	197.67
STA TO	BRIDGE OMISSION				
STA 81+07.50 TO 90+50	586.0	410.2	1013	(602.80)	-405.13
STA 90+50 TO 95+19.22	207.0	144.9	0	144.90	-260.23
TOTAL	1934	1354	1614	(260)	-260

FLEXIBLE PAVEMENT CONNECTOR		
LOCATION STA TO STA	WIDTH FT	FLEX PVT CONN SQ. YD
STA 79+95.50 TO STA 80+01.50	66	44
STA 81+37.50 TO STA 81+43.50	66	44
TOTAL		88

BRIDGE APPROACH PAVEMENT SCHEDULE		
LOCATION STA TO STA	WIDTH FT	BR APPR PVT SQ. YD
STA 80+01.50 TO STA 80+31.50	84	280
STA 81+07.50 TO STA 81+37.50	84	280
TOTAL		560

<b>COOMBE-BLOXDORF P.C.</b> Engineers / Land Surveyors Springfield, Illinois Design Firm License No. 184-002708	<b>REVISIONS</b> NAME      DATE		ILLINOIS DEPARTMENT OF TRANSPORTATION  <b>SCHEDULE OF QUANTITIES</b>  SCALE:      DRAWN BY CFC DATE AUG. 2008      CHECKED BY MCB/GLS	

10/17/2008 #FILE:ABBREV#