

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	*	PEORIA	186	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	IL RTE 29	
* (10,12)RS-6;1RS-4;(10B)BR				

LOCATION (STATION TO STATION)	LENGTH	4" THERMO YELLOW LN SOLID	4" THERMO YELLOW LN SKIP-DASH	PREF PLAS PAVT MRKG TY B - LN 6" SKIP-DASH	4" THERMO WHITE LN SOLID	24" THERMO WHITE LN SOLID	THERMO WH LETTERS & SYMBOLS	4" TEMP PVT MARKING LN
	FT	FT	FT	FT	FT	FT	FT	FT
STA 56+70 TO STA 61+50	480	960	240	240	960		124.8	2400
STA 61+50 TO STA 88+89	2739	3634	908.5	911	3644		624	9097.5
STA 88+89 TO STA 91+82.31	293.31	1516.62	369.16	146.655	586.62		78	2619.055
STA 91+82.31 TO STA 105+80	1397.69	2795.38	698.845	698.845	2795.38		358.8	6988.45
RELO. TR 103 STA 20+00 TO STA 37+55	1755		438.75					438.75
RELO. TR 103 STA 20+42						33		
STA 74+41, 40' RT (SHEFFIELD ST)						28		
TR 103 W STA 10+68						28		
TR 103 B STA 10+53						34		
<b>TOTAL</b>		<b>8906</b>	<b>2655</b>	<b>1997</b>	<b>7986</b>	<b>123</b>	<b>1186</b>	<b>21544</b>

LOCATION	TEMP CONC BARRIER	TEMP CONC BARRIER, RELOCATE
	FT	FT
<b>STAGE I</b>		
STA 63+30 TO STA 69+90	660	
STA 69+90 TO STA 76+50	660	
STA 76+50 TO STA 86+00	950	
STA 86+00 TO STA 89+30	330	
<b>STAGE II</b>		
STA 73+20 TO STA 76+50		330
STA 76+50 TO STA 86+00		950
STA 86+00 TO STA 92+60		660
STA 92+60 TO STA 99+20		660
<b>TOTALS</b>	<b>2600</b>	<b>2600</b>

LOCATION STATION TO STATION	LENGTH (FT)	REMOVAL (SQ FT)
TEMPORARY EDGE LINES STAGE I - STA 56+70 TO STA 105+80	4910	3053
TEMPORARY EDGE LINES STAGE II - STA 56+70 TO STA 105+80	4910	3053
SHORT-TERM EDGE LINES STA 56+70 TO 105+80 PRIOR TO SURF CSE	4910	19.15
SHORT-TERM SKIP-DASH STA 56+70 TO 105+80 PRIOR TO SURF CSE	4910	365.2
<b>TOTAL</b>		<b>6490</b>

LOCATION	IMPACT ATTENUATOR	IMPACT ATTENUATOR, RELOCATE
	EACH	EACH
<b>STAGE I</b>		
STA 63+20	1	
STA 89+30	1	
<b>STAGE II</b>		
STA 73+20		1
STA 99+20		1
<b>TOTALS</b>	<b>2</b>	<b>2</b>

STATION	R.R.P.M. CRYSTAL	R.R.P.M. AMBER	R.R.P.M. BRIDGE	R.R.P.M. REMOVAL
	EACH	EACH	EACH	EACH
STA 61+50 TO 68+70	18	36		18
STA 68+70 TO 70+50	5	9		14
STA 70+50 TO 75+27	12	24		12
STA 75+27 TO 77+92	7	13		20
STA 77+92 TO 84+24	14	29	4	18
STA 84+24 TO 88+89	12	23		35
STA 88+89 TO 91+82.31		15		0
<b>TOTALS</b>	<b>67</b>	<b>149</b>	<b>4</b>	<b>117</b>

LOCATION STATION TO STATION	LENGTH FT	REMOVAL SQ FT
CENTERLINES (4") STA 56+70 TO 105+80	4910	741.83
EDGE LINES (4") STA 56+70 TO 105+80	4910	2967.33
TURN-LANE LINES (4") STA 56+70 TO 105+80	4910	190.67
YELLOW TWLT LINES (4") STA 56+70 TO 105+80	4910	673.33
YELLOW TWLT SKIPS (4") STA 56+70 TO 105+80	4910	168.33
DOUBLE-YELLOW LINES (4") STA 56+70 TO 105+80	4910	1507.67
LEFT-TURN ARROWS	4910	265.20
12" YELLOW DIAGONALS STA 56+70 TO 105+80	4910	735.00
<b>TOTAL</b>		<b>7249</b>

LOCATION STATION TO STATION	LENGTH FT	SHORT TERM (3 APPS) FT
4" SKIP-DASH CENTERLINE STA 56+70 TO 105+80	4910	3286.8
SHORT-TERM EDGE LINES STA 76+50 TO 86+00	950	112.32
<b>TOTAL</b>		<b>3399</b>

**COOMBE-BLOXDORF P.C.**  
 Engineers / Land Surveyors  
 Springfield, Illinois  
 Design Firm License No. 184-002708

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 SCALE: DATE AUG. 2008  
 DRAWN BY CFC  
 CHECKED BY MCB/GLS

10/17/2008 9:15 AM BREVIS