

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6713	05-00148-00-PV	TAZEWELL	74	08
STA. 145+50.00		TO STA. 156+60.00		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

COMBINATION CONCRETE CURB AND GUTTER REMOVAL SCHEDULE			
LOCATION			COMB. CONC. CURB AND GUTTER REMOVAL FOOT
CAMP STREET			
STA. 145+48.00	TO	STA. 153+33.43	774.20
STA. 149+13.67	TO	STA. 153+15.90	401.60
STA. 154+81.49	TO	STA. 155+00.10	18.60
STA. 155+22.88	TO	STA. 156+19.97	98.60
SUBTOTAL			1,293.00
TOTAL			1,293

PAVEMENT REMOVAL SCHEDULE			
LOCATION			PAVEMENT REMOVAL SQ YD
CAMP STREET			
STA. 148+35.71	TO	STA. 153+61.70	1,571.30
STA. 154+62.18	TO	STA. 156+82.40	1,363.60
SUBTOTAL			2,934.90
TOTAL			2,935

DRIVEWAY PAVEMENT REMOVAL SCHEDULE			
LOCATION			DRIVEWAY PAVEMENT REMOVAL SQ YD
CAMP STREET			
STA. 149+51.16	TO	STA. 150+23.58	99.10
STA. 150+58.43	TO	STA. 151+25.46	77.70
STA. 151+27.29	TO	STA. 151+99.30	75.30
STA. 152+34.92	TO	STA. 152+89.62	55.84
SUBTOTAL			307.94
TOTAL			308

SPECIAL WASTE DISPOSAL			
LOCATION		SPECIAL WASTE DISPOSAL CU YD	
CAMP STREET			
STA. 145+48.00	TO	STA. 156+82.40	5,261.19
SUBTOTAL		5,261.19	
TOTAL		5,262	

EARTH SUMMARY SCHEDULE		
LOCATION	EARTH EXCAVATION CU YD	
CAMP STREET		
	1,899.00	
SUBTOTAL		1,899
TOTAL		1,899

STORM SEWER REMOVAL SCHEDULE					
LOCATION					
CAMP STREET					
STATION	TO	FROM	REMOVAL 12" FOOT	REMOVAL 15" FOOT	REMOVAL 24" FOOT
STA. 145+26.06	TO	STA. 148+26.21			296.00
STA. 148+26.20	TO	STA. 148+26.63	11.00		
STA. 148+26.21	TO	STA. 150+49.45		219.00	
STA. 148+30.27	TO				
STA. 150+48.78	TO	STA. 150+49.84	11.00		
STA. 150+48.78	TO				
STA. 150+49.45	TO				
STA. 150+49.45	TO	STA. 150+50.30	29.00		
STA. 150+49.84	TO	STA. 150+50.30	12.00		
STA. 150+53.18	TO				
STA. 150+53.83	TO				
SUBTOTAL			63	219	296
TOTAL			64	220	297

GUARDRAIL REMOVAL SCHEDULE			
LOCATION		GUARDRAIL REMOVAL FOOT	
CAMP STREET			
STA. 152+83.68	TO	STA. 153+53.31	71.00
SUBTOTAL		71.00	
TOTAL		71	

REMOVE EXISTING TEMPORARY TRAFFIC SIGNAL EQUIPMENT		
LOCATION	EA	
CAMP STREET		
	1.00	
SUBTOTAL		1.00
TOTAL		1

TEMP. EROSION CONTROL SEEDING SCHEDULE				
LOCATION			TEMPORARY EROSION CONTROL SEEDING LB	ACRE
CAMP STREET				
STA. 145+00.00	TO	STA. 156+36.00	237.000	0.790
STA. 148+35.00	TO	STA. 153+50.00	51.000	0.170
SUBTOTAL			288.000	0.960
TOTAL			288	1.00

PERMANENT SEEDING SCHEDULE							
LOCATION		SEEDING, CLASS 2A ACRE	NITROGEN FERTILIZER NUTRIENT POUND	PHOSPHORUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND	MULCH, METHOD 2 ACRE	TOPSOIL FURNISH AND PLACE, 4" SQ YD
CAMP STREET							
STA. 145+00.00	TO	STA. 156+36.00	0.790	71.10	71.10	0.790	3,823.60
STA. 148+35.00	TO	STA. 153+50.00	0.170	15.30	15.30	0.170	799.32
SUBTOTAL			0.960	86.40	86.40	0.960	4,622.92
TOTAL			1.0	86	86	1.0	4,624

INLET AND PIPE PROTECTION SCHEDULE				
LOCATION		DRAINAGE STRUCTURE	INLET AND PIPE PROTECTION EACH	INLET FILTERS EACH
CAMP STREET				
STA. 145+26.75	TO	STA. 147+00.00	101	1
STA. 147+00.00	TO	STA. 148+26.55	102	1
STA. 148+26.55	TO	STA. 150+42.80	104	1
STA. 150+42.80	TO	STA. 150+42.80	105	1
STA. 150+42.80	TO	STA. 152+18.50	106	1
STA. 152+18.50	TO	STA. 152+18.50	108	1
STA. 152+18.50	TO	STA. 150+42.80	109	1
STA. 150+42.80	TO		112	1
TOTAL			4	4

PERIMETER EROSION BARRIER SCHEDULE			
LOCATION			PERIMETER EROSION BARRIER FOOT
CAMP STREET			
STA. 153+84.16	TO	STA. 153+81.26	58.56
STA. 154+94.48	TO	STA. 155+42.50	83.50
SUBTOTAL			122.06
TOTAL			122

PAVING SCHEDULE												
LOCATION		BITUMINOUS MATERIALS (PRIME COAT) TON	AGGREGATE (PRIME COAT) TON	TEMPORARY RAMP SQ YD	PORTLAND CEMENT CONCRETE BASE COURSE 9 1/2" SQ YD	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX D, N70 TON	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 9" SQ YD	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED) SQ YD	BRIDGE APPROACH PAVEMENT SQ YD	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) SQ YD	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8" SQ YD	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION SQ YD
CAMP STREET				70.00								
STA. 151+55.59	CL	Driveway									31.07	
STA. 152+66.96	CL	Driveway									45.89	
STA. 155+15.46		Island						22.43				22.43
STA. 145+61.50	TO	STA. 149+18.67				1,084.63						1,084.63
STA. 149+18.67	TO	STA. 152+33.67				2,099.96						2,099.96
STA. 152+33.67	TO	STA. 153+34.16								166.93		
STA. 153+34.16	TO	STA. 153+63.15								166.55		
STA. 154+72.82	TO	STA. 156+01.14										1,045.00
STA. 155+01.14	TO	STA. 156+82.40	10.78	2.54	1,045.00	63.28	1,084.63	2,122.39	333.48	669.92	76.76	4,262.02
SUBTOTAL			10.78	2.54	1,045.00	63.28	1,084.63	2,122.39	333.48	669.92	76.76	4,262.02
TOTAL			10.8	3	1,045	64	1,085	2,123	334	670	77	4,263

AGGREGATE BASE SCHEDULE			
LOCATION		SUB-BASE GRANULAR MATERIAL, TYPE A 4" SQ YD	AGGREGATE BASE COURSE, TYPE A TON
CAMP STREET			
STA. 151+55.59	CL	Driveway	31.07
STA. 152+66.96	CL	Driveway	45.69
STA. 155+15.46		Island	15.90
STA. 145+61.50	TO	STA. 149+18.67	741.89
STA. 149+18.67	TO	STA. 152+33.67	1,436.37
STA. 155+01.14	TO	STA. 156+52.40	706.39
SUBTOTAL		76.76	2,900.55
TOTAL		77	2,901

MISCELLANEOUS PAVING			
LOCATION		HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT SQ YD	CLASS D PATCHES, TYPE IV, 8 INCH SQ YD
CAMP STREET			
STA. 150+50.00			43.50
STA. 156+52.40	TO	STA. 156+82.40	206.00
SUBTOTAL		206.00	43.50
TOTAL		206	44

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
CAMP STREET CONNECTOR
 SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE 12/22/2008

DRAWN BY JLT CHECKED BY CSA

L:\89392\DWG\SCHEDULE.DWG