

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6713	05-00148-00-PV	TAZEWELL	74	09
STA. 145+50.00		TO STA. 156+60.00		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

PIPE#	STR#	LOCATION	TRENCH BACKFILL	CONCRETE COLLAR	REINFORCEMENT BARS, EPOXY COATED	STORM SEWERS, CLASS A								MAN TA 5 DIA T1F OL	MAN TA 5 DIA T8G	INLETS TA T8G	INLETS TG-1 8PL	INLET-MAN TG-1 8D SP
						TYPE 1				TYPE 2								
						12" FT	15" FT	18" FT	21" FT	12" FT	18" FT	27" FT	30" FT					
CAMP STREET																		
US D/S																		
101		STA. 145+29.75	56.80 ft	RT														
102		STA. 147+00.00	50.00 ft	LT														
104		STA. 148+26.55	50.00 ft	RT														
105		STA. 150+42.80	30.00 ft	RT														
106		STA. 150+42.80	30.00 ft	LT														
108		STA. 152+18.50	30.00 ft	RT														
109		STA. 152+18.50	30.00 ft	LT														
111		STA. 148+26.55	3.20 ft	LT														
112		STA. 150+42.31	41.50 ft	LT														
101		STA. 145+29.75	56.80 ft	RT	TO STA. 145+26.06	9.96 ft	LT											
102		STA. 147+00.00	50.00 ft	LT	TO STA. 145+29.75	56.60 ft	RT											
103		STA. 148+26.55	46.00 ft	RT	TO STA. 147+00.00	30.00 ft	LT											
104		STA. 148+26.55	46.00 ft	RT	TO STA. 148+26.55	3.20 ft	LT	12.0										
105		STA. 148+26.55	50.00 ft	RT	TO STA. 150+42.80	30.00 ft	RT		51.0									
107		STA. 150+42.80	30.00 ft	LT	TO STA. 150+42.80	30.00 ft	RT	21.5		63.0								
108		STA. 152+18.50	30.00 ft	RT	TO STA. 150+42.80	30.00 ft	RT				63.0		172.0					
110		STA. 152+18.50	30.00 ft	LT	TO STA. 152+18.50	30.00 ft	RT	18.8										
111		STA. 150+42.80	41.50 ft	LT	TO STA. 150+42.80	30.00 ft	LT			7.0								
SUBTOTAL			52.4	0.4	27.0	70.0	51.0	212.0	119.0	63.0	172.0	166.0	65.0	1	2	1	2	
TOTAL			53.0	1.0	27.0	70.0	51.0	212.0	119.0	63.0	172.0	166.0	65.0	1	2	1	2	

CURB AND GUTTER SCHEDULE					
LOCATION	CONCRETE GUTTER	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24 (VARIABLE WIDTH GUTTER FLAG)	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06
LOCATION	FOOT	FOOT	FOOT	FOOT	FOOT
CAMP STREET					
STA. 145+48.00 TO STA. 156+20.00	RT	945.75			
STA. 149+13.67 TO STA. 153+18.40	LT	402.12			
STA. 155+15.38 TO STA. 155+25.49	LT				
STA. 155+24.67 TO STA. 155+29.05	LT		20.50		
STA. 155+12.94 TO STA. 155+18.91	LT			21.00	21.90
STA. 155+12.94 TO STA. 155+29.05	LT				
STA. 147+00.00		36.00			
STA. 148+26.55		16.00			
SUBTOTAL		52.00	1,347.87	20.50	21.00
TOTAL		52	1,348	21	22

ISLAND SCHEDULE	
LOCATION	CONCRETE MEDIAN SURFACE, 4 INCH SQ FT
CAMP STREET	
STA. 155+17.40 TO STA. 155+35.00	222.48
SUBTOTAL	
TOTAL	

GUARDRAIL SCHEDULE						
LOCATION	STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED
LOCATION	FOOT	EACH	EACH	EACH	EACH	EACH
CAMP STREET						
STA. 152+52.25 TO STA. 153+02.25	RT			1		1
STA. 152+90.20 TO STA. 153+14.31	LT					
STA. 153+02.25 TO STA. 153+27.25	RT	25.00			3	
STA. 153+27.25 TO STA. 153+71.00	RT		1			
STA. 154+67.08 TO STA. 155+40.83	RT		1			
STA. 155+40.83 TO STA. 156+15.83	RT	75.00			4	
STA. 156+15.83 TO STA. 156+65.83	RT			1		
SUBTOTAL		100.0	2	2	7	1
TOTAL		100	2	2	7	1

4' CHAIN LINK FENCE SCHEDULE		
LOCATION		FOOT
CAMP STREET		
STA. 153+79.09 TO STA. 153+95.10	RT	34
STA. 154+95.44 TO STA. 155+12.53	RT	34
SUBTOTAL		68
TOTAL		68

PERMANENT EPOXY PAVEMENT MARKING SCHEDULE											
LOCATION	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS, WHITE	EPOXY PAVEMENT MARKING - LINE 4"				EPOXY PAVEMENT MARKING - LINE 6"		EPOXY PAVEMENT MARKING - LINE 8"		EPOXY PAVEMENT MARKING - LINE 24"	
		WHITE	YELLOW	DBL. YEL.	YEL. SKIP	WHITE SKIP	WHITE	WHITE DIAG.	YELL. DIAG.	WHITE	
LOCATION	SQ FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	
CAMP STREET											
STA. 145+28.00 TO STA. 148+47.05				295.2							
STA. 145+61.60 TO STA. 151+03.30						138.0					
STA. 148+47.05 TO STA. 151+13.00				592.1							
STA. 148+47.05 TO STA. 151+13.00								94.8			
STA. 149+00.00 TO STA. 155+24.70	44.0										
STA. 151+13.00 TO STA. 158+02.00						160.0					
STA. 151+13.00 TO STA. 152+85.00					80.0						
STA. 151+13.00 TO STA. 151+85.00			344.6								
STA. 151+50.00 TO STA. 160+36.70						180.0					
STA. 152+85.00 TO STA. 155+05.00				220.0							
STA. 153+35.00 TO STA. 155+05.00								169.7			
STA. 154+84.60									18.0		
STA. 155+05.00									38.0		
STA. 155+39.20									12.4		
STA. 156+00.00 TO STA. 160+56.00				703.5							
STA. 156+00.00 TO STA. 158+40.00								126.8			
STA. 156+10.00									38.1		
STA. 158+02.00 TO STA. 158+39.56		36.1									
ALTON FER LANE											
STA. 9+54.05 TO STA. 12+02.90				257.5					193.9		
STA. 9+57.70 TO STA. 10+03.80						98.3		71.8			
STA. 10+03.80 TO STA. 10+95.30						91.8					
SUBTOTAL		44.0	36.1	344.6	2068.3	80.0	478.0	359.8	71.8	221.6	
TOTAL		44	36	344	2068	80	478	360	72	222	

ENGINEER'S FIELD OFFICE SCHEDULE	
LOCATION	ENGINEER'S FIELD OFFICE, TYPE A
LOCATION	GAL MO
ENTIRE PROJECT	
	22
SUBTOTAL	
TOTAL	

MOBILIZATION SCHEDULE	
LOCATION	MOBILIZATION
LOCATION	L. SUM
ENTIRE PROJECT	
	1
SUBTOTAL	
TOTAL	

TRAFFIC CONTROL AND PROTECTION SCHEDULE	
LOCATION	TRAFFIC CONTROL AND PROTECTION
LOCATION	L. SUM
ENTIRE PROJECT	
	1
SUBTOTAL	
TOTAL	

BARRIER SCHEDULE		
LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER
LOCATION	FOOT	FOOT
CAMP STREET		
STA. 152+10.00 TO STA. 156+40.00	RT	555.00
STA. 153+00.00 TO STA. 155+24.55	RT	200.00
SUBTOTAL		555
TOTAL		200

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
CAMP STREET CONNECTOR
SCHEDULE OF QUANTITIES

SCALE: VERT. DATE 12/22/2008
 DRAWN BY JLT
 CHECKED BY CSA

L:_B302P\DWG\SCHEDULE.DWG