

SUMMARY OF QUANTITIES			90% FED. 10% STATE	CONSTRUCTION TYPE CODE SFTY-2A	CONSTRUCTION TYPE CODE SFTY-2A	CONSTRUCTION TYPE CODE SFTY-2A	CONSTRUCTION TYPE CODE SFTY-2A	CONSTRUCTION TYPE CODE SFTY-2A	CONSTRUCTION TYPE CODE SFTY-2A	CONSTRUCTION TYPE CODE SFTY-2A	CONSTRUCTION TYPE CODE SFTY-2A	CONSTRUCTION TYPE CODE SFTY-2A
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	S.N. 026-0003	S.N. 026-0004	S.N. 026-0005	S.N. 026-0006	S.N. 026-0007	S.N. 026-0008	S.N. 026-0009	S.N. 026-0010	
20201500	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	500	63	63	57	66	61	61	63	66	
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SO YD	4391	556	550	498	579	538	538	553	579	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SO YD	5496	457	457	490	490	778	778	1023	1023	
44004250	PAVED SHOULDER REMOVAL	SO YD	4006	500	550	447	522	485	483	497	522	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	153	20	19	18	20	19	19	18	20	
50102400	CONCRETE REMOVAL	CU YD	148.6	10.4	10.3	23	23.1	26.9	26.9	14.1	13.9	
50300100	FLOOR DRAINS	EACH	71	14	14					21	22	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	164.7	18.4	18.4	23	23.1	26.9	26.9	14.1	13.9	
50300260	BRIDGE DECK GROOVING	SO YD	5208	433	433	464	464	737	737	970	970	
50300300	PROTECTIVE COAT	SO YD	5240	438	438	451	451	731	731	1000	1000	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3700							1850	1850	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	28							14	14	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	25150	1005	1005	4630	4630	4980	4980	1960	1960	
50800515	BAR SPLICERS	EACH	216	12	12	36	36	36	36	24	24	
51500200	RELOCATING NAME PLATES	EACH	6			1	1	1	1	1	1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	626			93	93	110	110	110	110	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	28							14	14	
52100520	ANCHOR BOLTS, 1"	EACH	56							28	28	
64200105	SHOULDER RUMBLE STRIP	FOOT	7903	1001	990	897	1041	969	967	995	1043	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	0.7	0.7	0.7	0.7	0.8	0.8	0.8	0.8	
67100100	MOBILIZATION	L SUM	1	0.13	0.12	0.13	0.12	0.13	0.12	0.13	0.12	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.13	0.12	0.13	0.12	0.13	0.12	0.13	0.12	
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1	0.13	0.12	0.13	0.12	0.13	0.12	0.13	0.12	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8	1	1	1	1	1	1	1	1	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	4666	1834	1833	1833	1833	1833	1833	1833	1834	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3375	362.5	362.5	375	375	437.5	437.5	512.5	512.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3375	362.5	362.5	375	375	437.5	437.5	512.5	512.5	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	34040	4255	4255	4255	4255	4255	4255	4255	4255	
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	4256	532	532	532	532	532	532	532	532	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	20	2	2	2	2	3	3	3	3	
X0321468	PLUG EXISTING DECK DRAINS	EACH	113					28	28	28	29	
X0325774	RELOCATE TEMPORARY IMPACT ATTENUATOR	EACH	8	1	1	1	1	1	1	1	1	
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SO YD	5240	438	438	451	451	731	731	1000	1000	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3572	507	372	391	424	391	424	462	601	
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SO YD	5240	438	438	451	451	731	731	1000	1000	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO YD	137	7	7	4	2		3	49	65	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	EACH	8	1	1	1	1	1	1	1	1	

Rev. 72-19-08

*Specialty Items

D-7 BRIDGE DECK REPAIRS

Rev.

FILE NAME =	USER NAME = swartzrw	DESIGNED -	REVISED -
ci:\pw\work\p\dot\swartzrw\dms50711\shitsq_94993.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	.	FAYETTE	59	3