



NOTES

1. BACKFILL MATERIAL FOR TRENCH BACKFILL (SPECIAL) AND FOR FRENCH DRAINS (SPECIAL) SHALL BE CA 14 WASHED GRAVEL.
2. SIDE WALLS OF TRENCHES FOR TRENCH BACKFILL (SPECIAL) AND FRENCH DRAIN (SPECIAL) SHALL BE LINED WITH GEOTECHNICAL FABRIC FOR FRENCH DRAINS AS SPECIFIED IN ARTICLE 601.06 OF THE STANDARD SPECIFICATIONS.
3. THE TOP 12 INCHES OF BACKFILL FOR PROPOSED CROSS ROAD UNDERDRAINS SHALL BE COMPACTED EARTH TO MATCH THE PROPOSED SUBGRADE ELEVATION. BACKFILL AT EXISTING CROSS ROAD UNDERDRAINS (STA 68+85 TO STA 89+50) SHALL BE REMOVED 20" DEEP AND REPLACED WITH MATERIAL TO MATCH THE EXISTING ROADWAY CROSS SECTION (12" COMPACTED EARTH, 8" CA 6). THE TOP 20 INCHES OF TRENCHES AT STA 57+00 AND STA 61+00 SHALL BE BACKFILLED WITH 12" OF COMPACTED EARTH AND 8" AGGREGATE BASE COURSE TYPE B. THIS WORK SHALL BE INCLUDED IN THE COST FOR AGGREGATE BASE COURSE TYPE B.

CUMMINS
ENGINEERING
CORPORATION

JOB = 2096.1	DESIGNED - NAK	REVISED -
FILE NAME = detail.dgn	DRAWN - AJH	REVISED -
PLOT SCALE = 20.0000 ft / IN.	CHECKED - NAK	REVISED -
PLOT DATE = 12/22/2008	DATE - 10/08/2008	REVISED -

**MOULTRIE COUNTY
BETHANY FINDLAY RD. IMPROVEMENTS**

BACKFILL DETAILS

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
650	02-00062-01-PV	MOULTRIE	44	15
CH 13, BETHANY FINDLAY RD.		CONTRACT NO. 95568		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				