

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	STRUCTURES
				ANDREWS DRIVE U. S. ROUTE 40 (FAU 9832) WOLF INDUSTRIAL DRIVE 99-00036-00-BR J000-2A	ANDREWS DRIVE OVER U. S. ROUTE 40 (S. N. 003-6000) 99-000-36-00-BR X531-2A
40603000	HOT-MIX ASPHALT BINDER COURSE, IL-12.5, N50	TON	438	438	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	342	342	
40701951	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/2"	SQ YD	3246	3246	
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	8257	8257	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	220	220	
42001300	PROTECTIVE COAT	SQ YD	8477	8477	
44000100	PAVEMENT REMOVAL	SQ YD	3151	3151	
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	3915	3915	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	348	348	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	514	514	
44003100	MEDIAN REMOVAL	SQ FT	180	180	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2813	2813	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	4060	4060	
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	90	90	
50200100	STRUCTURE EXCAVATION	CU YD	1116		1116
50300225	CONCRETE STRUCTURES	CU YD	259.9		259.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	401.7		401.7
50300260	BRIDGE DECK GROOVING	SQ YD	1141		1141
50300285	FORM LINER TEXTURED SURFACE	SQ FT	1040		1040
50300300	PROTECTIVE COAT	SQ YD	1512		1512
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	2250		2250
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	120300		120300
50800515	BAR SPLICERS	EACH	68		68
*50901730	BRIDGE FENCE RAILING	FOOT	340		340
*50901760	PIPE HANDRAIL	FOOT	289		289
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	540		540
51202305	DRIVING PILES	FOOT	540		540
*51203200	TEST PILE METAL SHELLS	EACH	1		1

* SPECIALTY ITEMS

USER NAME = Pop00836	DESIGNED - MH	REVISED -
PLOT SCALE = 1/8" = 1.0000' / in.	DRAWN - DJP	REVISED -
PLOT DATE = 12/29/2008	CHECKED - MH	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: 50 SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	99-00036-00-BR	BOND	99	4
CONTRACT NO. 97366				
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		