



K:\Springfield\0803508\Draw\Sheets
 FILE: EXCON01.dwg
 UPDATE BY: Kristy Brod
 PLOT DATE: 1/29/2009 12:18 PM
 SpAlign
 BASE_PROPOSED
 BASE_EXISTING

CA008

| REVISIONS | | |
|-----------|----|------|
| NUMBER | BY | DATE |
| | | |
| | | |
| | | |

0 1 2
 THIS BAR IS EQUAL TO 2'
 AT FULL SCALE (34X22).

LEGEND

- EXISTING PAVEMENT
- NEW PAVEMENT
- - - EXISTING JOINT
- SS — EXISTING STORM SEWER
- UD — EXISTING UNDERDRAIN
- - - EXISTING TXY B CIRCUIT
- FO — EXISTING FIBER OPTIC CABLE
- - - APPROXIMATE LEASE LINE
- ▭ EXISTING DUCT BANK
- ▭ EXISTING AIRFIELD SIGN
- ⊠ EXISTING BASE MOUNTED TXY LIGHT
- ⊙ EXISTING OVERHEAD LIGHT
- JB EXISTING JUNCTION BOX
- ⊙ SAN EXISTING SANITARY MANHOLE
- ⊙ SS EXISTING STORM SEWER MANHOLE
- ⊙ CS EXISTING COLLECTION STRUCTURE
- ⊙ CO EXISTING CLEANOUT
- EXISTING INLET
- EXISTING INSPECTION WELL
- ⊠ EXISTING SIGN
- GP EXISTING BOLLARD
- R REMOVAL

NOTES

- EXISTING EDGE LIGHT CABLING IS SHOWN DISTORTED TO IMPROVE CLARITY.
- REMOVAL OF SPLICE CANS WHICH ARE PART OF SIGN BASES SHALL BE INCIDENTAL TO SIGN BASE.

**SPRINGFIELD AIRPORT AUTHORITY
 ABRAHAM LINCOLN CAPITAL AIRPORT
 SPRINGFIELD, ILLINOIS**

**RECONSTRUCT AND EXPAND THE SOUTHEAST RAMP
 EXISTING CONDITIONS & REMOVALS**

© Copyright CMT, Inc.
CMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 184-000633

DESIGN BY: RLV/KLB
 DRAWN BY: CMT
 CHECKED BY: RW
 APPROVED BY: RW
 DATE: JANUARY 27, 2009
 JOB No: 08035-08
 IL PROJ. NO. SPI-3885
 AIP PROJ. NO. 3-17-0096-XX
 SHEET 09 OF 40 SHEETS

THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER, THE DIVISION, NOR THE PROJECT ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION.

IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE OWNER, AND THE RESIDENT ENGINEER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE OWNER AND THE ENGINEER.