

URBAN

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES		CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED 20% STATE 0013						
42001300	PROTECTIVE COAT	SO YD	263	263						
44200050	WELDED WIRE REINFORCEMENT	SO YD	220	220						
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	43	43						
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	112	112						
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SO YD	108	108						
44201299	DOWEL BARS 1 1/2"	EACH	300	300						
44213200	SAW CUTS	FOOT	1100	1100						
44213204	TIE BARS 3/4"	EACH	42	42						
50102400	CONCRETE REMOVAL	CU YD	6.3	6.3						
50300255	CONCRETE SUPERSTRUCTURE	CU YD	7.7	7.7						
50300300	PROTECTIVE COAT	SQ YD	38	38						
50606701	CLEANING AND PAINTING STRUCTURAL STEEL,	L SUM	1	1						
	LOCATION 1									
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1770	1770						
50800515	BAR SPLICERS	EACH	16	16						
<del>52000030</del>	<del>PREFORMED JOINT SEAL 2 1/2"</del>	<del>FOOT</del>	<del>204</del>	<del>204</del>						
52000005	PREFORMED JOINT SEAL 1"	FOOT	204	204						

SUMMARY OF QUANTITIES			TOTAL QUANTITIES		CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED 20% STATE 0013						
52000110	PREFORMED JOINT STRIP SEAL	FOOT	150	150						
52100500	ANCHOR BOLTS, 1/2"	EACH	32	32						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6						
67100100	MOBILIZATION	L SUM	1	1						
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	90	90						
70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	FOOT	5835	5835						
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	3300	3300						
* 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	420	420						
X0326766	CLEAN & RESEAL RELIEF JOINT	FOOT	160	160						
X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	SO FT	1310	1310						
X5870015	BRIDGE DECK CONCRETE SEALER	SO FT	7800	7800						
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1						
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SO FT	1945	1945						

REV. 2-21-2020

\* - SPECIALTY ITEMS

REV. - MS

FILE NAME =	USER NAME = senadestrad	DESIGNED -	REVISED -
p:\planroom\dtd\illinois\gov\PN1001\Documents\DOT	Offices\District\Projects\DI\B419\CAD\Draw\Design\DI\B419-st-	DRAWN -	REVISED -
	PLOT SCALE = 100,0000' / 1in	CHECKED -	REVISED -
	PLOT DATE = 12/13/2019	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

STRUCTURE NO. 045-2014  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
347	2019-057-BR	KANE	24	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 62J34	