



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 20, 2020

SUBJECT: Route Lincoln Prairie Trail  
Section 16-00112-00-BT (Charleston)  
Coles County  
Contract No.95849  
Item 182  
March 6, 2020 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices.**
- 2. Revised Sheet 2 of the Plans.**
- 3. Revised the Index to the Special Provisions.**
- 4. Revised page 4 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

## SPECIAL PROVISION INDEX

<b>Page #</b>	<b>Item</b>
1	Introduction
1	Description of Work
1	Traffic Control & Staging
2	ADA Compliance
2	Electric Transmission Lines
2	Seeding
3	Preparation of Base
3	Hot-Mix-Asphalt Surface Course, Mix "C", N70 Grading and
3	Shaping Shoulders
4	Remove Existing Sign Panel
4	Remove Existing Sign Post
4	Sign Panel - Type 1, and Telescoping Steel Sign Support
5	Utilities
6	LR107-4

**Remove Existing Sign Panel**

This work shall conform to Standard Specification Section 724 except as modified herein. This work shall consist of the removal and disposal of existing bike trail signs and posts at the locations shown in the plans.

This work will be paid at the contract unit price, per square foot, for Remove Existing Sign Panel – Type 1.

**Remove Existing Sign Post**

This work shall consist of the removal and disposal of existing Sign Posts at the locations shown in the plans.

This work will be paid at the contract unit price, each, for Remove Existing Sign Post. This item applies to existing posts without sign panels. The removal of Sign Posts that have Sign Panels attached are included in the cost of Remove Existing Sign Panels.

**Sign Panel - Type 1, and ~~Metal Post - Type A~~ Telescoping Steel Sign Support** 728  
This work shall conform to Standard Specification Sections 720 and ~~724~~, Standard 720001, Standard 720006, Standard 728001, Standard 729001, and the Plan Details for Pavement Markings & Signage except as modified herein. This work shall include furnishing and installing signs and posts at the locations shown in the plans.

All signage shall conform to the 2009 Edition of the Manual on Uniform Traffic Control Devices (MUTCD). Signs shall be Engineer Grade Reflective Sheeting or better. Backing shall be 0.08” Aluminum. Tops of posts shall be cut to the proper height.

All sign posts and anchors shall be driven. Direct burial will not be allowed due to the potential for encountering contaminated soil.

Signs will be paid at the contract unit price, per square foot, for Sign Panel - Type 1. Posts and Anchors will be paid at the contract unit price, per foot, for ~~Metal Post - Type A~~ Telescoping Steel Sign Support