SUMMARY OF QUANTITIES

	ITEM #	PAY ITEM	UNITS	QUANTITY
Δ	25000312	SEEDING, CLASS 4A	ACRE	3.3
Δ	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	297
Δ	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	297
Δ	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	297
Δ	25100115	MULCH, METHOD 2	ACRE	3.3
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	640
	28000400	PERIMETER EROSION BARRIER	FOOT	1,400
	35800100	PREPARATION OF BASE	SQUARE YARD	61,080
	40604002	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, MIX "C", N70	TON	5,873
	67100100	MOBILIZATION	LUMP SUM	1
Δ	72000100	SIGN PANEL - TYPE 1	SQFT	685
	72400310	REMOVE SIGN PANEL - TYPE 1	SQFT	526
⚠ Δ	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1,628
Δ	~~72900100~~	~~METAL POST - TYPE A~~	~~FOOT~~	~~1,628~~
Δ	78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQUARE FOOT	414
Δ	78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	19,224
Δ	78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	130
Δ	78009018	MODIFIED URETHANE PAVEMENT MARKING - LINE 18"	FOOT	2,049
	X0327979	PAVEMENT MARKING REMOVAL - GRINDING	SQUARE FOOT	1,880

SUMMARY OF QUANTITIES

ITEM #	PAY ITEM	UNITS	QUANTITY
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	925
Z0051398	REMOVE EXISTING SIGN POST	EACH	22

Δ SPECIALTY ITEMS

⚠ Revised 2/19/2020

HMA MIX DESIGN REQUIREMENTS	
	SURFACE
AC/PG:	PG 64-22
DESIGN AIR VOIDS:	4% @ Ndesign = 70
MIX COMPOSITION:	IL 9.5FGLB
FRICTION AGGREGATE:	MIX C
QUALITY MANAGEMENT:	QC/QA