

Summary of Quantities

#	Item	Section	Quantities					Totals	Unit	Rates/Remarks
			Shield's Chapel Rd.	Taylor Rd.	McKinley Rd.	Conservation Rd.	Gale Rd.			
1	Special Clearing	201	0.1	0.1	0.1	0.3	0.4	1	L.S.	
2	Earth Excavation	202	30	-	-	4,759	23,193	27,982	C.Y.	Compaction Required Per S.P. 205
3	Seeding	250	0.2	-	-	2.1	6.5	8.8	Acre	Aug. 15 - Sept. 15, 2008
4	Nitrogen Fertilizer Nutrient	250	24	-	-	252	780	1,056	Pound	120 Lbs./Acre
5	Phosphorous Fertilizer Nutrient	250	40	-	-	420	1,300	1,760	Pound	200 Lbs/Acre
6	Potassium Fertilizer Nutrient	250	60	-	-	630	1,950	2,640	Pound	300 Lbs/Acre
7	Agricultural Ground Limestone	250	1	-	-	4	13	18	Ton	2 Tons/Acre
8	Mulch, Method 2, Procedure 1	IDOT 251	0.2	-	-	1.6	5.3	7.1	Acre	2 Tons/Acre
9	Erosion Control Blanket	IDOT 251	109	-	-	2,417	6,031	8,557	S.Y.	
10	Stone Riprap A-3	IDOT 281	61	-	255	-	-	316	S.Y.	
11	Stone Riprap C-4	IDOT 281	-	-	-	3,486	5,809	9,295	Ton	
12	Stone Riprap A-1	IDOT 281	-	-	-	583	663	1,246	Ton	
13	Filter Fabric for use with Riprap	IDOT 282	61	-	255	1,265	1,427	3,008	S.Y.	
14	Bituminous Materials (Cover and Seal Coat)	IDOT 403	-	-	-	2,934	-	2,934	Gallon	
15	Cover Coat Aggregate	IDOT 403	-	-	-	123	-	123	Ton	
16	Seal Coat Aggregate	IDOT 403	-	-	-	62	-	62	Ton	
17	Steel Plate Beam Guard Rail, Type A	IDOT 630	175	330	1,340	400	1,681	3,926	Foot	
18	Traffic Barrier Terminals, Type 1	IDOT 631	2	2	10	2	12	28	Each	
19	Delineators, Terminal Marker Placement, Case II	IDOT 635	2	2	10	2	12	28	Each	
20	Delineators, Reflector Marker, Type A	IDOT 635	4	7	27	8	34	80	Each	50 Foot Spacing
21	Woven Wire Fence - 4' High	IDOT 665	226	-	145	690	1,433	2,494	Foot	
22	Mobilization	671	0.2	0.2	0.2	0.2	0.2	1	L.S.	
23	Traffic Control and Protection Standard 701201	IDOT 701	0.2	0.2	0.2	0.2	0.2	1	L.S.	
24	Traffic Control and Protection Standard 701206	IDOT 701	0.2	0.2	0.2	0.2	0.2	1	L.S.	

CONSTRUCTION NOTES

BURIAL/REMOVAL OF MATERIAL—Concrete and masonry debris designated for burial by the engineer shall be buried at least three feet below proposed final grade. Onsite organic debris and trash shall be disposed of in an engineer approved offsite landfill in accordance with Sections 201 and 501 of the Special Provisions.

TREE REMOVAL—Trees removed shall be disposed of onsite per Section 201 of the Special Provisions.

EROSION CONTROL—The contractor shall schedule his operations and take such precautions that may be necessary to prevent or minimize erosion. Failure to comply with this requirement shall cause the contractor to be fully responsible for repairing any eroded areas and cleaning up areas or drainage structures that have become silted in or damaged.

AGRICULTURAL GROUND LIMESTONE—Immediately prior to seed bed preparation, fertilizer nutrients and agricultural ground limestone shall be uniformly spread at the rates specified in the plans.

MULCHING—Within 24 hours from the time seeding has been performed, the seeded area shall be given a covering of mulch at the rates specified in the plans. The mulch is to be anchored into the soil in accordance with the requirements for method 2, procedure 1 of Article 251.03 of the Standard Specifications. If Excelsior or Special Excelsior Blanket is to be used, the blanket shall be placed the same day that the areas are seeded.

GENERAL NOTES

Unless otherwise noted on the plans, all disturbed areas within the construction limits will be amended with agricultural ground limestone, fertilizer nutrients, seeded and mulched at the required rates specified in the plans.

The contractor is responsible for visiting the site and familiarizing himself with the existing conditions and the proposed reclamation work prior to submitting a bid.

The contractor shall provide and pay for all field engineering services to execute the project as specified in the Field Engineering section of the Special Provisions.

The contractor is responsible for locating and protecting all existing utility lines pertaining to the work.

Unless noted on the plans, all onsite access roads may be used for construction and must be maintained during construction and restored to original or better condition at the completion of work by the contractor. Access roads to the site as designated in the plans are to be maintained to the satisfaction of the engineer.

The construction limits will be staked by the contractor prior to construction. The contractor is responsible for the repair and or restitution at his own expense for all damages done to any area outside the construction limits.

Application rates specified in the plans are shown in the Summary of Quantities—Rates/Remarks column.