

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	1 Y-B-R-1	LAKE	121	5a
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		ROADWAY 1000-2A	BICYCLE PATH/SIDEWALK SFTY-1B	BRIDGE X020-2A	TRAFFIC SIGNAL INVERARY Y031-1F	TRAFFIC SIGNAL DEERFIELD Y031-1F	TRAFFIC SIGNAL INTERCONN Y031-1F	CODE NO	ITEM	UNIT		ROADWAY 1000-2A	BICYCLE PATH/SIDEWALK SFTY-1B	BRIDGE X020-2A	TRAFFIC SIGNAL INVERARY 1000-2A	TRAFFIC SIGNAL DEERFIELD 1000-2A	TRAFFIC SIGNAL INTERCONN 1000-2A
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1			1													
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1			1													
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1				1												
X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1				1												
XX003136	CATCH BASIN TYPE C	EACH	2	2															
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5		0.5													
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2															
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2															
MX033290	SEDIMENT CONTROL, SILT FENCE	METER	50	50															
M5428124	PRECAST REINFORCED CONCRETE FLARED END SECTION 525MM	EACH	1	1															
M5505540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 375MM	METER	73	73															
M5505930	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 300MM	METER	271	271															
M5505940	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 375MM	METER	26	26															
M5505960	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 525 MM	METER	95	95															
M5505970	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 600MM	METER	183	183															
M5505990	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 750MM	METER	6	6															
MX703200	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III	METER	4000	4000															
X0325938	TEMPORARY WIRELESS INTERCONNECT, COMPLETE	L SUM	1			0.5	0.5												
* 06900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1															
* 06900530	SOIL DISPOSAL ANALYSIS	EACH	1	1															
* M6690100	BACKFILL PLUGS	CU M	58	58															
* M6690200	NON-SPECIAL WASTE DISPOSAL	CU M	505	505															
MX032200	ENGINEERED BARRIER	SQ. M	1510	1510															

① 80% FED. 20% STATE  
 ② 50% STATE 50% VILLAGE OF BUFFALO GROVE  
 ③ 80% FED. 20% STATE  
 ④ 80% FED. 13.3% STATE 6.7% VERNON TWP.  
 ⑤ 80% FED. 10% STATE 5% BUFFALO GROVE  
 ⑥ 80% FED. 20% STATE 5% LAKE COUNTY

\* SPECIALTY ITEMS  
 Rev. 2-28-08  
 Rev. 2-22-08

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 US 45/IL 21  
 OVER APTAKISIC CREEK  
 SUMMARY OF QUANTITIES