

**SUMMARY OF QUANTITIES**

F.A.P. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
308 INHJH-LVBJH-2R	ROCK ISLAND	210	5
STA. TO STA.		FED. AID PROJECT	
FED. ROAD DIST. NO. 2		ILLINOIS	

CODE NUMBER	ITEM	URBAN 80% FED. 20% STATE		BRF ROADWAY BITUMINOUS 1000	BRF ROADWAY CONCRETE J000	BRF BRIDGE 31ST SB X271-2A	BRF BRIDGE 31ST NB X271-2A	BRF BRIDGE RR X171 2A	BRF BRIDGE 18TH X271-2A	BRF BRIDGE 7TH X271-2A	BRF GUARDRAIL SFTY-3J	BRF LIGHTING Y030-1E
		UNITS	TOTAL									
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	475	475								
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	475	475								
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	475	475								
20200100	EARTH EXCAVATION	CU YD	83	83								
20400800	FURNISHED EXCAVATION	CU YD	2250	2250								
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1252			138	138	348	310	318		
20800150	TRENCH BACKFILL	CU YD	193.8	193.8								
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	991	991								
21400100	GRADING AND SHAPING DITCHES	FOOT	100	100								
25000210	SEEDING, CLASS 2A	ACRE	5.3	5.3								
25000750	MOWING	ACRE	5.3	5.3								
28000700	MULCH, METHOD 1	ACRE	21.2	21.2								
25100115	MULCH, METHOD 2	ACRE	5.3	5.3								
25100630	EROSION CONTROL BLANKET	SQ YD	25525	25525								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2112	2112								
28000400	PERIMETER EROSION BARRIER	FOOT	9955	9955								
28000500	INLET AND PIPE PROTECTION	EACH	39	39								
28100125	STONE RIPRAP, CLASS B3	SQ YD	134	134								
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	5960	5960								
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	91	91								
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1015	1015								
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	567	567								
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	108		108							
42000520	PORTLAND CEMENT CONCRETE PAVEMENT 11"	SQ YD	5714		5714							
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	2129		2129							
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	444		444							
42101300	PROTECTIVE COAT	SQ YD	14168		14168							
44000100	PAVEMENT REMOVAL	SQ YD	108		108							
44000155	HOT-MIX ASPHALT SURFACE COURSE REMOVAL, 1 1/2"	SQ YD	1255		1255							
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	5489		5489							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	418		418							
44000700	APPROACH SLAB REMOVAL	SQ YD	2116		2116							
44004250	PAVED SHOULDER REMOVAL	SQ YD	12605		12605							
44200571	CLASS A PATCHES, TYPE IV, 11 INCH	SQ YD	691		691							
48101200	AGGREGATE SHOULDERS, TYPE B	TON	178		178							
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	12067		12067							
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1						1			
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1						1			

●

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: NONE	DRAWN BY AMK	CHECKED BY MGZ
DATE		

PLOT DATE \* DATE \*  
FILE NAME \* FILE \*  
USER NAME \* USER \*

● NON-PARTICIPATING (100% STATE)

**SUMMARY OF QUANTITIES**