

# SCHEDULE OF QUANTITIES

| F.A.P. RTE.           | SECTION          | COUNTY           | TOTAL SHEETS | SHEET NO. |
|-----------------------|------------------|------------------|--------------|-----------|
| 308                   | 1048B-1,4B,8B-ZR | ROCK ISLAND      | 210          | 13        |
| STA.                  |                  | TO STA.          |              |           |
| FED. ROAD DIST. NO. 2 | ILLINOIS         | FED. AID PROJECT |              |           |

### 40603340 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70

| TON        | LOCATION                 | SHEET    | REMARKS |
|------------|--------------------------|----------|---------|
| 0          | 1451+00.00 TO 1457+00.00 | SHEET 1  |         |
| 0          | 1457+00.00 TO 1463+00.00 | SHEET 2  |         |
| 13         | 1463+00.00 TO 1469+00.00 | SHEET 3  |         |
| 63         | 1469+00.00 TO 1475+00.00 | SHEET 4  |         |
| 0          | 1475+00.00 TO 1481+00.00 | SHEET 5  |         |
| 0          | 1481+00.00 TO 1487+00.00 | SHEET 6  |         |
| 0          | 1487+00.00 TO 1493+00.00 | SHEET 7  |         |
| 0          | 1493+00.00 TO 1499+00.00 | SHEET 8  |         |
| 0          | 1499+00.00 TO 1504+00.00 | SHEET 9  |         |
| 134        | 1504+00.00 TO 1510+00.00 | SHEET 10 |         |
| 0          | 1510+00.00 TO 1515+00.00 | SHEET 11 |         |
| 146        | 1515+00.00 TO 1521+00.00 | SHEET 12 |         |
| 25         | 1521+00.00 TO 1527+00.00 | SHEET 13 |         |
| 0          | 1527+00.00 TO 1533+00.00 | SHEET 14 |         |
| 0          | 1533+00.00 TO 1539+00.00 | SHEET 15 |         |
| 0          | 1539+00.00 TO 1545+00.00 | SHEET 16 |         |
| 80         | 1545+00.00 TO 1551+00.00 | SHEET 17 |         |
| 0          | 1551+00.00 TO 1557+00.00 | SHEET 18 |         |
| 0          | 1557+00.00 TO 1561+63.55 | SHEET 19 |         |
| 39         | 1469+00.00 TO 1475+00.00 | SHEET 4  | STAGE 1 |
| 33         | 1515+00.00 TO 1521+00.00 | SHEET 12 | STAGE 1 |
| 34         | 1545+00.00 TO 1551+00.00 | SHEET 17 | STAGE 1 |
| <u>567</u> | TOTAL                    |          |         |

### 42000501 PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)

| SQ_YD      | LOCATION       | OFFSET | DIRECTION | REMARKS      |
|------------|----------------|--------|-----------|--------------|
| 54         | 7TH AVE BRIDGE |        |           | NORTH OF 7TH |
| 54         | 7TH AVE BRIDGE |        |           | SOUTH OF 7TH |
| <u>108</u> | TOTAL          |        |           |              |

### 42000520 PORTLAND CEMENT CONCRETE PAVEMENT 11"

| SQ_YD        | LOCATION                 | SHEET    | REMARKS |
|--------------|--------------------------|----------|---------|
| 0            | 1451+00.00 TO 1457+00.00 | SHEET 1  |         |
| 0            | 1457+00.00 TO 1463+00.00 | SHEET 2  |         |
| 0            | 1463+00.00 TO 1469+00.00 | SHEET 3  |         |
| 0            | 1469+00.00 TO 1475+00.00 | SHEET 4  |         |
| 0            | 1475+00.00 TO 1481+00.00 | SHEET 5  |         |
| 215          | 1481+00.00 TO 1487+00.00 | SHEET 6  |         |
| 474          | 1487+00.00 TO 1493+00.00 | SHEET 7  |         |
| 439          | 1493+00.00 TO 1499+00.00 | SHEET 8  |         |
| 355          | 1499+00.00 TO 1504+00.00 | SHEET 9  |         |
| 363          | 1504+00.00 TO 1510+00.00 | SHEET 10 |         |
| 357          | 1510+00.00 TO 1515+00.00 | SHEET 11 |         |
| 385          | 1515+00.00 TO 1521+00.00 | SHEET 12 |         |
| 474          | 1521+00.00 TO 1527+00.00 | SHEET 13 |         |
| 508          | 1527+00.00 TO 1533+00.00 | SHEET 14 |         |
| 485          | 1533+00.00 TO 1539+00.00 | SHEET 15 |         |
| 469          | 1539+00.00 TO 1545+00.00 | SHEET 16 |         |
| 394          | 1545+00.00 TO 1551+00.00 | SHEET 17 |         |
| 455          | 1551+00.00 TO 1557+00.00 | SHEET 18 |         |
| 341          | 1557+00.00 TO 1561+63.55 | SHEET 19 |         |
| <u>5,714</u> | TOTAL                    |          |         |

### 42001165 BRIDGE APPROACH PAVEMENT

| SQ_YD        | LOCATION        | OFFSET | DIRECTION | REMARKS       |
|--------------|-----------------|--------|-----------|---------------|
| 139          | 31ST AVE BRIDGE |        | NB        | SOUTH OF 31ST |
| 139          | 31ST AVE BRIDGE |        | SB        | SOUTH OF 31ST |
| 139          | 31ST AVE BRIDGE |        | NB        | NORTH OF 31ST |
| 139          | 31ST AVE BRIDGE |        | SB        | NORTH OF 31ST |
| 281          | RR BRIDGE       |        |           | SOUTH OF RR   |
| 283          | RR BRIDGE       |        |           | NORTH OF RR   |
| 252          | 18TH AVE BRIDGE |        |           | SOUTH OF 18TH |
| 253          | 18TH AVE BRIDGE |        |           | NORTH OF 18TH |
| 252          | 7TH AVE BRIDGE  |        |           | SOUTH OF 7TH  |
| 253          | 7TH AVE BRIDGE  |        |           | NORTH OF 7TH  |
| <u>2,129</u> | TOTAL           |        |           |               |

### 42001420 BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)

| SQ_YD      | LOCATION        | OFFSET | DIRECTION | REMARKS       |
|------------|-----------------|--------|-----------|---------------|
| 28         | 31ST AVE BRIDGE |        | NB        | SOUTH OF 31ST |
| 28         | 31ST AVE BRIDGE |        | SB        | SOUTH OF 31ST |
| 28         | 31ST AVE BRIDGE |        | NB        | NORTH OF 31ST |
| 28         | 31ST AVE BRIDGE |        | SB        | NORTH OF 31ST |
| 72         | RR BRIDGE       |        |           | SOUTH OF RR   |
| 56         | RR BRIDGE       |        |           | NORTH OF RR   |
| 51         | 18TH AVE BRIDGE |        |           | SOUTH OF 18TH |
| 51         | 18TH AVE BRIDGE |        |           | NORTH OF 18TH |
| 51         | 7TH AVE BRIDGE  |        |           | SOUTH OF 7TH  |
| 51         | 7TH AVE BRIDGE  |        |           | NORTH OF 7TH  |
| <u>444</u> | TOTAL           |        |           |               |

### 44000100 PAVEMENT REMOVAL

| SQ_YD      | LOCATION       | OFFSET | DIRECTION | REMARKS      |
|------------|----------------|--------|-----------|--------------|
| 54         | 7TH AVE BRIDGE |        |           | NORTH OF 7TH |
| 54         | 7TH AVE BRIDGE |        |           | SOUTH OF 7TH |
| <u>108</u> | TOTAL          |        |           |              |

### 44000155 HOT-MIX ASPHALT SURFACE COURSE REMOVAL, 1 1/2"

| SQ_YD        | LOCATION        | OFFSET | DIRECTION | REMARKS |
|--------------|-----------------|--------|-----------|---------|
| 463          | 31ST AVE BRIDGE |        | NB        |         |
| 392          | 18TH AVE BRIDGE |        | NB        |         |
| 400          | 7TH AVE BRIDGE  |        | NB        |         |
| <u>1,255</u> | TOTAL           |        |           |         |

PLOT DATE \* DATE \*  
 FILE NAME \* FILE \*  
 USER NAME \* USER \*

| REVISIONS |      | ILLINOIS DEPARTMENT OF TRANSPORTATION |
|-----------|------|---------------------------------------|
| NAME      | DATE |                                       |
|           |      |                                       |
|           |      |                                       |
|           |      |                                       |
|           |      |                                       |
|           |      |                                       |
|           |      |                                       |
|           |      |                                       |
|           |      |                                       |
|           |      |                                       |
|           |      |                                       |

SCALE: NONE  
 DATE: \_\_\_\_\_ DRAWN BY: JW  
 CHECKED BY: MGZ

## SCHEDULE OF QUANTITIES