

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
308	118B,118-1,118B,118-2R	ROCK ISLAND	210	14
STA. TO STA.				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				

44000198 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH

SQ YD	LOCATION	SHEET	REMARKS
0	1451+00.00 TO 1457+00.00	SHEET 1	
0	1457+00.00 TO 1463+00.00	SHEET 2	
156	1463+00.00 TO 1469+00.00	SHEET 3	
745	1469+00.00 TO 1475+00.00	SHEET 4	
0	1475+00.00 TO 1481+00.00	SHEET 5	
0	1481+00.00 TO 1487+00.00	SHEET 6	
0	1487+00.00 TO 1493+00.00	SHEET 7	
0	1493+00.00 TO 1499+00.00	SHEET 8	
0	1499+00.00 TO 1504+00.00	SHEET 9	
1597	1504+00.00 TO 1510+00.00	SHEET 10	
0	1510+00.00 TO 1515+00.00	SHEET 11	
1735	1515+00.00 TO 1521+00.00	SHEET 12	
303	1521+00.00 TO 1527+00.00	SHEET 13	
0	1527+00.00 TO 1533+00.00	SHEET 14	
0	1533+00.00 TO 1539+00.00	SHEET 15	
0	1539+00.00 TO 1545+00.00	SHEET 16	
953	1545+00.00 TO 1551+00.00	SHEET 17	
0	1551+00.00 TO 1557+00.00	SHEET 18	
0	1557+00.00 TO 1561+63.55	SHEET 19	
5,489	TOTAL		

44004250 PAVED SHOULDER REMOVAL

SQ YD	LOCATION	SHEET	REMARKS
0	1451+00.00 TO 1457+00.00	SHEET 1	
0	1457+00.00 TO 1463+00.00	SHEET 2	
1131	1463+00.00 TO 1469+00.00	SHEET 3	
1397	1469+00.00 TO 1475+00.00	SHEET 4	
930	1475+00.00 TO 1481+00.00	SHEET 5	
915	1481+00.00 TO 1487+00.00	SHEET 6	
877	1487+00.00 TO 1493+00.00	SHEET 7	
980	1493+00.00 TO 1499+00.00	SHEET 8	
1481	1499+00.00 TO 1504+00.00	SHEET 9	
859	1504+00.00 TO 1510+00.00	SHEET 10	
1337	1510+00.00 TO 1515+00.00	SHEET 11	
1086	1515+00.00 TO 1521+00.00	SHEET 12	
371	1521+00.00 TO 1527+00.00	SHEET 13	
0	1527+00.00 TO 1533+00.00	SHEET 14	
0	1533+00.00 TO 1539+00.00	SHEET 15	
267	1539+00.00 TO 1545+00.00	SHEET 16	
925	1545+00.00 TO 1551+00.00	SHEET 17	
49	1551+00.00 TO 1557+00.00	SHEET 18	
0	1557+00.00 TO 1561+63.55	SHEET 19	
12,605	TOTAL		

44000500 COMBINATION CURB AND GUTTER REMOVAL

FOOT	LOCATION	OFFSET	DIRECTION	REMARKS
88	18TH AVE BRIDGE			SOUTH OF 18TH
88	18TH AVE BRIDGE			NORTH OF 18TH
87	7TH AVE BRIDGE			SOUTH OF 7TH
87	7TH AVE BRIDGE			NORTH OF 7TH
17	1499+26.77	-37.56		
15	1514+07.69	-82.04		
18	1522+92.92	-38.39		
18	1543+70.43	37.22		
418	TOTAL			

44200571 CLASS A PATCHES, TYPE IV, 11 INCH

SQ YD	LOCATION	OFFSET	DIRECTION	REMARKS
41	1469+41.30		NB	SOUTH OF 31ST
41	1469+68.80		SB	SOUTH OF 31ST
40	1471+71.80		NB	NORTH OF 31ST
40	1471+99.40		SB	NORTH OF 31ST
54	1505+19.30		NB	SOUTH OF RR
77	1505+58.00		SB	SOUTH OF RR
66	1508+59.00		NB	NORTH OF RR
104	1509+17.50		SB	NORTH OF RR
27	1516+70.00		SB	SOUTH OF 18TH
29	1516+73.20		NB	SOUTH OF 18TH
27	1519+82.00		SB	NORTH OF 18TH
29	1519+84.30		NB	NORTH OF 18TH
30	1546+15.00		NB	SOUTH OF 7TH
29	1546+16.70		SB	SOUTH OF 7TH
29	1548+28.50		SB	NORTH OF 7TH
28	1548+29.10		NB	NORTH OF 7TH
691	TOTAL			

44000700 APPROACH SLAB REMOVAL

SQ YD	LOCATION	SHEET	REMARKS
0	1451+00.00 TO 1457+00.00	SHEET 1	
0	1457+00.00 TO 1463+00.00	SHEET 2	
0	1463+00.00 TO 1469+00.00	SHEET 3	
481	1469+00.00 TO 1475+00.00	SHEET 4	
0	1475+00.00 TO 1481+00.00	SHEET 5	
0	1481+00.00 TO 1487+00.00	SHEET 6	
0	1487+00.00 TO 1493+00.00	SHEET 7	
0	1493+00.00 TO 1499+00.00	SHEET 8	
0	1499+00.00 TO 1504+00.00	SHEET 9	
785	1504+00.00 TO 1510+00.00	SHEET 10	
0	1510+00.00 TO 1515+00.00	SHEET 11	
428	1515+00.00 TO 1521+00.00	SHEET 12	
0	1521+00.00 TO 1527+00.00	SHEET 13	
0	1527+00.00 TO 1533+00.00	SHEET 14	
0	1533+00.00 TO 1539+00.00	SHEET 15	
0	1539+00.00 TO 1545+00.00	SHEET 16	
422	1545+00.00 TO 1551+00.00	SHEET 17	
0	1551+00.00 TO 1557+00.00	SHEET 18	
0	1557+00.00 TO 1561+63.55	SHEET 19	
2,116	TOTAL		

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: NONE	DRAWN BY JW	
DATE	CHECKED BY MGZ	

PLOT DATE \* \* \* \* \*  
 FILE NAME \* \* \* \* \*  
 USER NAME \* \* \* \* \*

## SCHEDULE OF QUANTITIES