

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
30B	IHB,HB-LVB,HB-2R	ROCKY ISLAND	210	17
STA.	TO STA.			
FED. ROAD DIST. NO. 2	ILLINOIS	FED. AID PROJECT		

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6

EACH	LOCATION	OFFSET	DIRECTION	REMARKS
1	1469+39.78 TO 1469+83.53	OUTSIDE EOS	NB	31ST
1	1469+57.54 TO 1470+01.29	INSIDE EOS	NB	31ST
1	1471+39.34 TO 1471+83.09	INSIDE EOS	SB	31ST
1	1471+57.10 TO 1472+00.85	OUTSIDE EOS	SB	31ST
1	1505+04.25 TO 1505+47.49	OUTSIDE EOS	NB	IAIS RR
1	1508+96.55 TO 1509+40.54	OUTSIDE EOS	SB	IAIS RR
1	1516+80.91 TO 1517+25.24	OUTSIDE EOS	NB	18TH
1	1518+34.98 TO 1518+78.63	OUTSIDE EOS	SB	18TH
1	1546+18.66 TO 1546+63.04	OUTSIDE EOS	NB	7TH
1	1547+80.52 TO 1548+24.53	OUTSIDE EOS	SB	7TH
10 TOTAL				

63500105 DELINEATORS

EACH	LOCATION	OFFSET	DIRECTION	REMARKS
1	1464+14.78	OUTSIDE EOS	NB	
1	1467+32.56	INSIDE EOS	NB	
1	1474+07.99	INSIDE EOS	SB	
1	1477+25.85	OUTSIDE EOS	SB	
1	1479+19.46	INSIDE EOS	NB	SIGN TRUSS
1	1485+51.03	INSIDE EOS	SB	TYPE D GUARDRAIL
1	1485+51.03	INSIDE EOS	NB	TYPE D GUARDRAIL
1	1498+59.47	OUTSIDE EOS	NB	
1	1514+08.59	OUTSIDE EOS	NB	
1	1514+47.58	OUTSIDE EOS	SB	
1	1521+54.33	OUTSIDE EOS	SB	
1	1543+38.74	OUTSIDE EOS	NB	
1	1550+96.54	OUTSIDE EOS	SB	
13 TOTAL				

63100089 TRAFFIC BARRIER TERMINAL, TYPE 6B

EACH	LOCATION	OFFSET	DIRECTION	REMARKS
1	1484+94.79 TO 1485+51.03	INSIDE EOS	SB	31ST
1	1484+94.79 TO 1485+51.03	INSIDE EOS	SB	31ST
2 TOTAL				

63700255 CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT

FOOT	LOCATION	OFFSET	SHEET	REMARKS
0	1451+00.00 TO 1457+00.00		SHEET 1	
0	1457+00.00 TO 1463+00.00		SHEET 2	
0	1463+00.00 TO 1469+00.00		SHEET 3	
0	1469+00.00 TO 1475+00.00		SHEET 4	
0	1475+00.00 TO 1481+00.00		SHEET 5	
149	1481+00.00 TO 1487+00.00		SHEET 6	
600	1487+00.00 TO 1493+00.00		SHEET 7	
600	1493+00.00 TO 1499+00.00		SHEET 8	
500	1499+00.00 TO 1504+00.00		SHEET 9	
311	1504+00.00 TO 1510+00.00		SHEET 10	
500	1510+00.00 TO 1515+00.00		SHEET 11	
366	1515+00.00 TO 1521+00.00		SHEET 12	
600	1521+00.00 TO 1527+00.00		SHEET 13	
600	1527+00.00 TO 1533+00.00		SHEET 14	
600	1533+00.00 TO 1539+00.00		SHEET 15	
600	1539+00.00 TO 1545+00.00		SHEET 16	
366	1545+00.00 TO 1551+00.00		SHEET 17	
600	1551+00.00 TO 1557+00.00		SHEET 18	
464	1557+00.00 TO 1561+63.55		SHEET 19	
6,856 TOTAL				

63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

EACH	LOCATION	OFFSET	DIRECTION	REMARKS
1	1464+14.78 TO 1464+64.78	OUTSIDE EOS	NB	31ST
1	1467+32.64 TO 1467+82.64	INSIDE EOS	NB	31ST
1	1473+57.99 TO 1474+07.99	INSIDE EOS	SB	31ST
1	1476+75.85 TO 1477+25.85	OUTSIDE EOS	SB	31ST
1	1479+19.46 TO 1479+69.46	MEDIAN		N. OF 31ST
1	1498+62.07 TO 1499+11.82	OUTSIDE EOS	NB	IAIS RR
1	1513+96.95 TO 1514+45.25	OUTSIDE EOS	SB	IAIS RR
1	1514+09.44 TO 1514+58.78	OUTSIDE EOS	NB	18TH
1	1522+66.13 TO 1523+16.13	OUTSIDE EOS	SB	18TH
1	1543+40.06 TO 1543+90.71	OUTSIDE EOS	NB	7TH
1	1550+46.66 TO 1550+96.01	OUTSIDE EOS	SB	7TH
11 TOTAL				

63801205 TEMPORARY MODULAR GLARE SCREEN

FOOT	LOCATION	OFFSET	DIRECTION	REMARKS
500	1456+00.00 TO 1461+00.00		SB	
300	1556+00.00 TO 1559+00.00		SB	
350	1556+50.00 TO 1560+00.00		NB	
1,150 TOTAL				

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION	OFFSET	DIRECTION	REMARKS
433	1465+50.36 TO 1469+82.93	OUTSIDE EOS	NB	
363	1466+67.21 TO 1470+30.03	OUTSIDE EOS	SB	
137	1468+65.57 TO 1470+00.61	INSIDE EOS	NB	
349	1471+10.59 TO 1474+59.85	OUTSIDE EOS	NB	
110	1471+39.94 TO 1472+49.17	INSIDE EOS	SB	
382	1471+57.70 TO 1475+39.13	OUTSIDE EOS	SB	
572	1477+85.95 TO 1483+46.31	OUTSIDE EOS	SB	
637	1479+14.95 TO 1485+51.03	INSIDE EOS	NB	
725	1499+05.27 TO 1506+39.82	OUTSIDE EOS	SB	
341	1502+08.09 TO 1505+44.25	OUTSIDE EOS	NB	
431	1507+85.03 TO 1512+04.16	OUTSIDE EOS	NB	
532	1508+99.05 TO 1514+32.07	OUTSIDE EOS	SB	
321	1514+06.62 TO 1517+22.66	OUTSIDE EOS	NB	
480	1518+33.76 TO 1523+15.63	OUTSIDE EOS	SB	
303	1543+54.74 TO 1546+61.05	OUTSIDE EOS	NB	
235	1547+82.46 TO 1550+13.88	OUTSIDE EOS	SB	
289.5	1471+33.00 TO 1474+01.00	LT EOS	SB	STAGE 3
289.5	1467+77.00 TO 1470+30.00	RT EOS	NB	STAGE 4
6,930 TOTAL				

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	OFFSET	DIRECTION	REMARKS
1	31ST AVE BRIDGE			
1	RR BRIDGE			
1	18TH AVE BRIDGE			
1	7TH AVE BRIDGE			
4 TOTAL				

PLOT DATE * * * * *
FILE NAME * * * * *
PLOT SCALE * * * * *
USER NAME * * * * *

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SCALE: NONE
DATE

DRAWN BY JW
CHECKED BY MGZ

SCHEDULE OF QUANTITIES