

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	117 T	OGLE	86	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	TOTAL QUANTITY	80% Federal 20% State Y007
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1	1
50105200	REMOVE EXISTING CULVERTS	EACH	2	2
51205200	TEMPORARY SHEET PILING	SG FT	6441	6441
51500100	NAME PLATES	EACH	5	5
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2	2
54001003	BOX CULVERT END SECTIONS, CULVERT NO. 3	EACH	1	1
54001004	BOX CULVERT END SECTIONS, CULVERT NO. 4	EACH	1	1
54001005	BOX CULVERT END SECTIONS, CULVERT NO. 5	EACH	2	2
54010605	PRECAST CONCRETE BOX CULVERT 6' X 5'	FOOT	109	109
54010704	PRECAST CONCRETE BOX CULVERT 7' X 4'	FOOT	123.5	123.5
54010804	PRECAST CONCRETE BOX CULVERT 8' X 4'	FOOT	236	236
54010806	PRECAST CONCRETE BOX CULVERT 8' X 6'	FOOT	95	95
54207807	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM, EQUIVALENT ROUND-SIZE 42"	FOOT	114	114
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	68	68
54200241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	47	47
54213063	PIPE CULVERTS, TYPE 3, REINFORCED, CONC. - ARCH, EQUIVALENT, ROUND-SIZE 48"	FOOT	118	118
54213453	END SECTIONS 18"	EACH	1	1
54213471	END SECTIONS 36"	EACH	2	2
54214317	END SECTIONS, EQUIVALENT ROUND-SIZE 42"	EACH	4	4
54214953	PRECAST REINFORCED CONCRETE FLARED END SECTIONS-ARCH, EQUIVALENT ROUND-SIZE 48"	EACH	4	4
54210024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	390	390
54248180	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 48"	EACH	4	4
61100500	EXPLORATION TRENCH 52' DEPTH	FOOT	60	60
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	1	1
63200310	GUARDRAIL REMOVAL	FOOT	1550	1550
63500105	DELINEATORS	EACH	10	10
66500105	WOVEN WIRE FENCE, 4'	FOOT	500	500
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	37	37

PLOT DATE = Fri Dec 28 14:22:19 2007  
 FILE NAME = c:\proj\joe\y210705\dl0705wr.dgn  
 PLOT SCALE = 50.0000 / IN.  
 USER NAME = gortj