

SCHEDULES OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	117 T	OGLE	86	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

54010605	PRECAST CONCRETE BOX CULVERT 6' X 5'			REMARKS
	FOOT	LOCATION		
	109	Sta. 1081+12.7		

54213453	END SECTIONS 18"			
	EACH	LOCATION	OFFSET (ft)	REMARKS
	1	RT Sta. 813+18.8	28.35	PE/ Box # 2

54010704	PRECAST CONCRETE BOX CULVERT 7' X 4'			REMARKS
	FOOT	LOCATION		
	123.5	Sta. 1056+26.4		22.54 degrees skew

54213471	END SECTIONS 36"			
	EACH	LOCATION	OFFSET (ft)	REMARKS
	2	RT Sta. 1126+39.0	39.24	PE/ Box # 5

54010804	PRECAST CONCRETE BOX CULVERT 8' X 4'			REMARKS
	FOOT	LOCATION		
	236	Sta. 1125+82.0		26 degrees skew
	DBL-CELL OF 118 FT			

54214317	END SECTIONS, EQUIVALENT ROUND-SIZE 42"			
	EACH	LOCATION	OFFSET (ft)	REMARKS
	2	RT Sta. 1115+77.5	37.23	FE
	2	RT Sta. 1117+53.2	37.23	FE
	4	TOTAL		

54010806	PRECAST CONCRETE BOX CULVERT 8' X 6'			REMARKS
	FOOT	LOCATION		
	95	Sta. 812+63.4		BOX # 2

54214953	PRECAST REINF CONC FLARED END SECTION-ARCH EQUIVALENT, ROUND-SIZE 48"			REMARKS
	EACH	LOCATION		
	4	LT & Rt Sta. 803+63.4		BOX 1

54207807	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM, EQUIVALENT ROUND-SIZE 42"			REMARKS
	FOOT	LOCATION	OFFSET (ft)	
	57	RT Sta. 1115+77.5	37.23	
	57	RT Sta. 1117+53.2	37.23	
	114	TOTAL		

5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)			
	FOOT	LOCATION	OFFSET (ft)	REMARKS
	60	Sta. 803+63.0		STAGING
	90	Sta. 812+64.0		STAGING
	90	Sta. 1056+40.0		STAGING
	80	Sta. 1081+10.0		STAGING
	70	Sta. 1125+82.0		STAGING
	390	TOTAL		

NOTE: TEMPORARY PIPE TO BE USED IF NECESSARY TO MAINTAIN FLOW DURING STAGE CONSTRUCTION.

542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"			
	FOOT	LOCATION	OFFSET (ft)	REMARKS
	68	RT Sta. 812+51.8 TO 813+19.8	27.97	PE/ Box # 2

542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"			
	FOOT	LOCATION	OFFSET (ft)	REMARKS
	47	RT Sta. 1126+39.0	48.88	'RT TO 40.66 Box # 5

54248180	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 48"			
	EACH	LOCATION		REMARKS
	4	RT Sta. 803+63.4		BOX 1

54213063	PIPE CULVERTS, TYPE 3, REINFORCED, CONC-ARCH EQUIVALENT, ROUND SIZE 48"			REMARKS
	FOOT	LOCATION		
	118	LT & Rt Sta. 803+63.4		BOX 1

61100500	EXPLORATION TRENCH 52" DEPTH			
	FOOT	LOCATION	OFFSET (ft)	REMARKS
	60	RT Sta. 1125+45.0 TO 1125+75.0		75' RT-20'RT*EXPOSE ALL FIELD TILES UP TO CONSTRUCTION LIMITS

PLOT DATE = Fri Dec 28 13:52:59 2007
 FILE NAME = c:\p\objects\1210705\d10705bvr.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = gpfj