

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	117 T	OGLE	86	27
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULES OF QUANTITIES

Z0030070 IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 3

EACH	LOCATION	REMARKS
	BOX # 2	
1	Lt Sta. 813+01.4	STAGE 1

Z0030250 IMPACT ATTENUATOR, TEMPORARY (NON-DEDUCTIBLE), TEST LEVEL 3

EACH	LOCATION	REMARKS
	BOX # 2	
1	Lt Sta. 811+01.9	STAGE 1
1	Lt Sta. 814+25.8	STAGE 2
	BOX # 3	
1	Lt Sta. 1054+89.3	STAGE 1
1	Lt Sta. 1057+63.7	STAGE 1
	BOX # 4	
1	Lt Sta. 1079+50.6	STAGE 1
1	Lt Sta. 1082+74.9	STAGE 1
	BOX # 5	
1	Lt Sta. 11+14.0	STAGE 1
1	Lt Sta. 1127+56.3	STAGE 1
8	TOTAL	

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDUCTIVE), TEST LEVEL 3

EACH	LOCATION	REMARKS
	BOX # 2	
1	Rt Sta. 811+01.9	STAGE 2
	BOX # 3	
1	Rt Sta. 1054+27.0	STAGE 2
1	Rt Sta. 1058+25.9	STAGE 2
	BOX # 4	
1	Rt Sta. 1079+75.5	STAGE 2
1	Rt Sta. 1082+49.9	STAGE 2
	BOX # 5	
1	Rt Sta. 1123+69.8	STAGE 2
1	Rt Sta. 1127+93.7	STAGE 2
7	TOTAL	

Z0020900 ESTABLISHING AND REFERENCING

LAND SECTION	MARKERS	LOCATION	OFFSET (ft)	REMARKS
EACH		Rt Sta. 1118+56.0	4	
1				

Z007530	TIE BARS 3/4"	LOCATION	PATCH LENGTH	LANE WIDTH(FT)	REMARKS
	EACH	RT Sta. R-LANE		12	BOX 1
	12.00	LT Sta. LT- LANE	40	12	BOX 1
	32.00	RT Sta. R-LANE		12	BOX 2
	12.00	LT Sta. LT- LANE	62	12	BOX 2
	43.00	RT Sta. R-LANE		12	BOX 3
	12.00	LT Sta. LT- LANE	64	12	BOX 3
	44.00	RT Sta. R-LANE		12	BOX 4
	12.00	LT Sta. LT- LANE	54	12	BOX 4
	39.00	RT Sta. R-LANE		12	BOX 5
	12.00	LT Sta. LT- LANE	72	12	BOX 5
	48.00 TOTAL				
	266				

TIE BARS ARE INSTALLED AT 24 INCHES CENTERS

PLOT DATE = Fri, Dec 28, 13:52:48, 2007
 FILE NAME = c:\projects\117\11705\11705.dwg
 PLOT SCALE = 1/8" = 1' IN.
 USER NAME = gpfj