

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
654	109M	CARROLL	76	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

70301000	WORK ZONE PAVEMENT MARKING REMOVAL		LOCATION	REMARKS
	WHITE SQ. FT.	YELLOW	IL 73	
	312		RT Sta. 263+00	TO 272+44
	312		LT Sta. 263+00	TO 272+44
	165		RT Sta. 273+00	TO 278+00
	165		LT Sta. 273+00	TO 278+00
		363	Sta. 263+00	TO 278+00
		165	Sta. 274+00	TO 274+00
			<i>Payne Road</i>	
	72		RT Sta. 23+00	TO 25+18
	72		LT Sta. 23+00	TO 25+18
	133		RT Sta. 28+47	TO 32+50
	133		LT Sta. 28+47	TO 32+50
		72	Sta. 23+00	TO 25+18
		133	Sta. 28+47	TO 32+50
			<i>South Bolton Rd</i>	
		40	Sta. 700+35	TO 701+55
			L & R Sta. 700+11	TO 702+00
			<i>IL 72/ Shannon Rd</i>	
			L & R Sta. 60+13	TO 61+24
			<i>South Bolton Rd/ Pearl City Rd</i>	
			LT Sta. 798+42	TO 799+88
			<i>Pearl City Rd</i>	
			Pearl City Rd structure	
			1/4 ml. east of Miche Rd	
	1749	773	TOTAL	
	2522			

78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"		LOCATION	OFFSET (ft)	REMARKS
	FOOT		IL 73		
	24		<i>Payne Road</i>		
	24		RT Sta. 26+40		Stop bar White
			LT Sta. 27+22		Stop bar White
			<i>South Bolton Rd</i>		
	26		LT Sta. 700+40		Stop bar White
			<i>IL 72/ Shannon Rd</i>		
	28		LT Sta. 60+40		Stop bar White
	102	TOTAL			

X0323455	ADJUST MONITORING WELL		LOCATION	OFFSET (ft)	REMARKS
	EACH		IL 73		
	1		LT Sta. 212+62	28.0	
	1		<i>Shannon Road</i>		
	1		LT Sta. 60+38	16.0	
	1		LT Sta. 60+79	10.5	
	1		LT Sta. 61+09	12.5	
	4	TOTAL			

78001110	PAINT PAVEMENT MARKING - LINE 4"		LOCATION (2 APPLICATIONS)	OFFSET (ft)	REMARKS
	WHITE	YELLOW	IL 73		
	1889		RT Sta. 263+00	TO 272+44	White Edge line Right
	1889		LT Sta. 263+00	TO 272+44	White Edge line Left
	1000		RT Sta. 273+00	TO 278+00	White Edge line Right
	1000		LT Sta. 273+00	TO 278+00	White Edge line Left
	2200	4400	Sta. 263+00	TO 274+00	Double Yellow -Center line
		1000	Sta. 274+00	TO 278+00	Solid RT/ Skip LT
			<i>Payne Road</i>		
	436		RT Sta. 23+00	TO 25+18	White Edge line Right
	436		LT Sta. 23+00	TO 25+18	White Edge line Left
	806		RT Sta. 28+47	TO 32+50	White Edge line Right
	806		LT Sta. 28+47	TO 32+50	White Edge line Left
		872	Sta. 23+00	TO 25+18	Double Yellow -Center line
		1612	Sta. 28+47	TO 32+50	Double Yellow -Center line
			<i>South Bolton Rd</i>		
		480	Sta. 700+35	TO 701+55	Double Yellow -Median
			L & R Sta. 700+11	TO 702+00	White Edge line Right
			<i>IL 72/ Shannon Rd</i>		
			L & R Sta. 60+13	TO 61+24	White Edge line Right
			<i>South Bolton Rd/ Pearl City Rd</i>		
			LT Sta. 798+42	TO 799+88	White Edge line Right
	12407	8364	TOTAL		
	20771				

X0323660	DROP BOX NO.1		LOCATION	OFFSET (ft)	REMARKS
	EACH		IL 73		
	1		RT Sta. 268+22.6		6'X8'X8' DROP STRUCTURE

X0325519	DRAIN FOR AGGREGATE BASE COURSE		LOCATION	OFFSET (ft)	REMARKS
	SQ. YD.		IL 73		
	3		L & R Sta. 265+00.0		
	3		L & R Sta. 268+22.0		
	3		L & R Sta. 272+00.0		
	3		L & R Sta. 277+00.0		
	3		<i>Payne Road</i>		
	15	TOTAL	L & R Sta. 29+50.0		

78001150	PAINT PAVEMENT MARKING - LINE 12"		LOCATION	OFFSET (ft)	REMARKS
	FOOT		IL 73		
	50		<i>South Bolton Rd</i>		
			Sta. 700+35	TO 701+55	Diagonals @ 20' Centers Yellow

Z0020900	ESTABLISHING AND REFERENCING LAND SECTION MARKERS		LOCATION	OFFSET (ft)	REMARKS
	EACH		IL 73		
	1		LT Sta. 272+43.0	5	

Note: CONTRACTOR SHALL CALL Kurt Glazier from the Bureau of operation prior to striping. see GENERAL NOTES.

Tue Feb 05 11:32:51 2008
 c:\p\projects\2008\946\946.dwg
 08/08/08 / JN
 gortj

PLOT DATE
 FILE NAME
 PLOT SCALE
 USER NAME