

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FAS	FAP	FAS	FAP
				I-000	I-000	X-081-2A	X-081-2A
				ROADWAY US 6 SN 037-0131	ROADWAY IL 78 SN 037-0129	BRIDGE US 6 SN 037-0131	BRIDGE IL 78 SN 037-0129
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
44213100	PAVEMENT FABRIC	SQ YD	243	243			
44213200	SAW CUTS	FOOT	868	868			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	105	85	20		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	642	295	347		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2			1	1
50102400	CONCRETE REMOVAL	CU YD	8.3			4.0	4.3
50300225	CONCRETE STRUCTURES	CU YD	9.3			5.2	4.1
50300260	BRIDGE DECK GROOVING	SQ YD	1079			583	496
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	5434			2975	2459
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	4535			2529	2006
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16200			9040	7160
50800515	BAR SPLICERS	EACH	297			144	153
50901050	STEEL RAILING, TYPE SM	FOOT	648			269	379
51500100	NAME PLATES	EACH	2			1	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	106			42	64
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	387.5	312.5	75		
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	8	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2			
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	6	2	4		
63200310	GUARDRAIL REMOVAL	FOOT	1065	608	457		

* SPECIALTY ITEMS