

70400100	TEMPORARY CONCRETE BARRIER	Location	Sta.	EQOI	Remarks
US 6	663+15.0	-	670+10.0	700.0	Stage I
US 6 Total =				700.0	
IL 78	879+03.4	-	886+09.5	707.0	Stage I
IL 78 Total =				707.0	
Grand Total =				1407.0	

70400200	RELOCATE TEMPORARY CONCRETE BARRIER	Location	Sta.	EQOI	Remarks
US 6	663+31.0	-	669+94.0	675.0	Stage II
US 6 Total =				675.0	
IL 78	879+03.4	-	886+09.5	707.0	Stage II
IL 78 Total =				707.0	
Grand Total =				1382.0	

78001110	PAINTE PAVEMENT MARKING - LINE 4"	Location	Sta.	to	Sta.	EQOI	Remarks
US 6	661+22.9	-	666+03.2	LT	240.2	CL skip dash - Yellow (2 coats)	
	661+22.9	-	666+03.2	RT	960.6	CL solid stripe - Yellow (2 coats)	
	666+03.2	-	672+50.0	RT	323.4	CL skip dash - Yellow (2 coats)	
	666+03.2	-	672+50.0	LT	1293.6	CL solid stripe - Yellow (2 coats)	
US 6	661+22.9	-	672+50.0	LT	2254.2	White Edge Line (2 coats)	
	661+22.9	-	672+50.0	RT	2254.2	White Edge Line (2 coats)	
US 6 Total =				7326.2			
IL 78	881+01.1	-	884+34.5	LT	666.9	CL solid stripe - Yellow (2 coats)	
	881+01.1	-	884+34.5	RT	666.9	CL solid stripe - Yellow (2 coats)	
	881+01.1	-	884+34.5	LT	666.9	White Edge Line (2 coats)	
	881+01.1	-	884+34.5	RT	666.9	White Edge Line (2 coats)	
IL 78 Total =				2667.4			
Grand Total =				9993.6			

78100100	RAISED REFLECTIVE PAVEMENT MARKER	Location	Sta.	to	Sta.	EACH	Remarks
US 6	661+22.9	-	672+50.0	Median	14	Two-way Amber	
	US 6 Total =				14		
IL 78	881+01.1	-	884+34.5		4	Two-way Amber	
IL 78 Total =				4			
Grand Total =				18			

78200410	GUARDRAIL MARKERS, TYPE A	Location	Sta.	EACH	Remarks
US 6	664+45.0	-	668+18.4	RT	8
	665+20.0	-	669+05.9	LT	8
US 6 Total =				16	
IL 78	880+90.1	-	884+08.1	RT	8
	881+27.6	-	884+45.6	LT	8
IL 78 Total =				16	
Grand Total =				32	

78201000	TERMINAL MARKER - DIRECT APPLIED	Location	Sta.	EACH	Remarks
US 6	663+95.0			RT	1
	664+70.0			LT	1
	668+70.2			RT	1
	669+57.7			LT	1
US 6 Total =				4	
IL 78	880+40.1			RT	1
	880+77.6			LT	1
	884+58.1			RT	1
	884+95.6			LT	1
IL 78 Total =				4	
Grand Total =				8	

78300100	PAVEMENT MARKING REMOVAL	Location	Sta.	SO FI	Remarks
US 6	662+99.1	-	670+59.1	253.3	Stage II
	US 6 Total =				253.3
IL 78	879+39.5	-	885+68.0	209.5	Stage II
	IL 78 Total =				209.5
Grand Total =				462.8	

X7030100	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III	Location	Sta.	EQOI	Remarks
US 6	661+46.0	-	671+52.0	1008.0	Stage I - Inside
	661+96.0	-	672+02.0	1008.0	Stage II - Inside
US 6 Total =				2016.0	
IL 78	877+76.8	-	887+90.6	1016.0	Stage I - Inside
	877+21.7	-	887+34.9	1016.0	Stage II - Inside
IL 78 Total =				2032.0	
Grand Total =				4048.0	

Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	Location	Sta.	EACH	Remarks
US 6	663+14.7			RT	1
	670+10.0			RT	1
US 6 Total =				2	
IL 78	879+03.4			LT	1
	886+09.5			LT	1
IL 78 Total =				2	
Grand Total =				4	

Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	Location	Sta.	EACH	Remarks
US 6	663+30.6			LT	1
	669+94.3			LT	1
US 6 Total =				2	
IL 78	879+03.4			RT	1
	886+09.5			RT	1
IL 78 Total =				2	
Grand Total =				4	

* FAP 22 (IL 78) & FAS 1247 (US 6) ** (125BR-1)D & (6BR)D

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -
c:\projects\p205007\d05007cwr.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	HENRY	80	14
CONTRACT NO. 64D10			ILLINOIS FED. AID PROJECT	