

SUMMARY OF QUANTITIES CONT.

CODE NUMBER	ITEM	UNIT	URBAN			
			TOTAL QUANTITY	90% FED 10% STATE	HSIP 1000-1A	NHS 1000-1A
			90% FED 7.5% STATE 2.5% COUNTY	HSIP Y031-1F	80% FED 20% STATE	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	171	18	153	
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	3,524	3,524		
50100300	REMOVAL OF EXISTING STRUCTURE NO. 1	EACH	1	1		
50100400	REMOVAL OF EXISTING STRUCTURE NO. 2	EACH	1	1		
50100500	REMOVAL OF EXISTING STRUCTURE NO. 3	EACH	1	1		
50105200	REMOVE EXISTING CULVERTS	EACH	1	1		
51500100	NAME PLATES	EACH	2	2		
54010602	PRECAST CONCRETE BOX CULVERT 6' X 2'	FOOT	144	144		
54010702	PRECAST CONCRETE BOX CULVERT 7' X 2'	FOOT	180	180		
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	86	86		
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	96	96		
542D5479	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	40	40		
54214299	END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	2	2		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2		
60500040	REMOVING MANHOLES	EACH	1	1		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	308	308		
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	110	110		
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	18	18		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	515	515		
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	350	350		
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	5	5		
61140000	STORM SEWERS (SPECIAL) 8"	FOOT	155	155		
61140100	STORM SEWERS (SPECIAL) 10"	FOOT	50	50		
61140200	STORM SEWERS (SPECIAL) 12"	FOOT	227	227		
63500105	DELINATORS	EACH	6	6		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	51	51		
66700305	PERMANENT SURVEY MARKER, TYPE II	EACH	2	2		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	2	2		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	45	45		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5,975	5,646	329	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21,464	21,464		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	116	116		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	112	112		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	664	627	37	
* 72000100	SIGN PANEL - TYPE I	SQ FT	12		12	
* 72000200	SIGN PANEL - TYPE II	SQ FT	18		18	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	312	312		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21,348	19,156	2,192	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2,215	2,215		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,832	1,832		

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*303	129M&TS	WINNEBAGO	110	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(IL 173)

PLOT DATE = Tue Dec 04 08:25:05 2007
 FILE NAME = c:\p\proj\ecis\2007\707\d89797.rvt.dgn
 PLOT SCALE = 0.25412 / IN.
 REFERENCE = REF#