

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*303	129M&TS	WINNEBAGO	110	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION
IL 173	
7	Sta 237+16 40' LT
14	Sta 248+11 101' RT
ARGYLE ROAD	
7	Sta 93+49 26' RT
6	Sta 94+05 26' RT
10	Sta 94+10 27' RT
BELVIDERE ROAD	
8	Sta 101+15 40' LT
8	Sta 101+97 37' LT
6	Sta 102+03 36' LT
8	Sta 102+48 55' RT
11	Sta 107+76 39' LT
6	Sta 107+76 35' LT
6	Sta 107+76 38' LT
11	Sta 107+86 40' LT
108	TOTAL

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION
IL 173	
27	Sta 239+97 27' LT
38	Sta 253+11 28' RT
38	Sta 254+62 35' RT
48	Sta 254+68 32' LT
36	Sta 256+33 31' LT
40	Sta 258+74 35' RT
BELVIDERE ROAD	
48	Sta 101+79 43' LT
18	Sta 102+58 61' RT
22	Sta 102+58 62' RT
24	Sta 102+78 39' LT
18	Sta 104+95 40' LT
357	TOTAL

20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

CU YD	LOCATION
IL 173	
85.9	Sta 244+47.5
ARGYLE ROAD	
21.8	Sta 99+00
BELVIDERE ROAD	
62.7	Sta 104+93
170.4	TOTAL

25000210 SEEDING, CLASS 2A

ACRE	LOCATION
IL 173	
1.1	Sta 230+50 - 260+13 LT
1.5	Sta 230+50 - 260+13 RT
ARGYLE ROAD	
0.4	Sta 93+00 - 100+00 LT
0.4	Sta 93+00 - 100+00 RT
BELVIDERE ROAD	
0.3	Sta 100+00 - 109+54 LT
0.4	Sta 100+00 - 109+54 RT
4.1	TOTAL

25000400 NITROGEN FERTILIZER NUTRIENT

POUND	LOCATION	90 LBS/ACRE
IL 173		
99	Sta 230+50 - 260+13	LT
135	Sta 230+50 - 260+13	RT
ARGYLE ROAD		
36	Sta 93+00 - 100+00	LT
36	Sta 93+00 - 100+00	RT
BELVIDERE ROAD		
27	Sta 100+00 - 109+54	LT
36	Sta 100+00 - 109+54	RT
369	TOTAL	

25000500 PHOSPHORUS FERTILIZER NUTRIENT

POUND	LOCATION	90 LBS/ACRE
IL 173		
99	Sta 230+50 - 260+13	LT
135	Sta 230+50 - 260+13	RT
ARGYLE ROAD		
36	Sta 93+00 - 100+00	LT
36	Sta 93+00 - 100+00	RT
BELVIDERE ROAD		
27	Sta 100+00 - 109+54	LT
36	Sta 100+00 - 109+54	RT
369	TOTAL	

25000600 POTASSIUM FERTILIZER NUTRIENT

POUND	LOCATION	90 LBS/ACRE
IL 173		
99	Sta 230+50 - 260+13	LT
135	Sta 230+50 - 260+13	RT
ARGYLE ROAD		
36	Sta 93+00 - 100+00	LT
36	Sta 93+00 - 100+00	RT
BELVIDERE ROAD		
27	Sta 100+00 - 109+54	LT
36	Sta 100+00 - 109+54	RT
369	TOTAL	

25000750 MOWING

ACRE	LOCATION
IL 173	
1.1	Sta 230+50 - 260+13 LT
1.5	Sta 230+50 - 260+13 RT
ARGYLE ROAD	
0.4	Sta 93+00 - 100+00 LT
0.4	Sta 93+00 - 100+00 RT
BELVIDERE ROAD	
0.3	Sta 100+00 - 109+54 LT
0.4	Sta 100+00 - 109+54 RT
4.1	TOTAL

25100115 MULCH, METHOD 2

ACRE	LOCATION	(Areas subtracted out for Erosion Blanket)
IL 173		
0.6	Sta 230+50 - 260+13	LT
0.9	Sta 230+50 - 260+13	RT
ARGYLE ROAD		
0.3	Sta 93+00 - 100+00	LT
0.3	Sta 93+00 - 100+00	RT
BELVIDERE ROAD		
0.1	Sta 100+00 - 109+54	LT
0.2	Sta 100+00 - 109+54	RT
2.4	TOTAL	

25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION	Width = 8'
IL 173		
2,635	Sta 230+50 - 260+13	LT
2,635	Sta 230+50 - 260+13	RT
ARGYLE ROAD		
622	Sta 93+00 - 100+00	LT
622	Sta 93+00 - 100+00	RT
BELVIDERE ROAD		
848	Sta 100+00 - 109+54	LT
848	Sta 100+00 - 109+54	RT
8,210	TOTAL	

25100900 TURF REINFORCEMENT MAT

SQ YD	LOCATION
ARGYLE ROAD	
67	Sta 98+75 - 99+00 LT
80	Sta 98+75 - 99+00 RT
147	TOTAL

28000250 TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION	6 APPLICATIONS X 100 LBS / ACRE
IL 173		
660	Sta 230+50 - 260+13	LT
900	Sta 230+50 - 260+13	RT
ARGYLE ROAD		
240	Sta 93+00 - 100+00	LT
240	Sta 93+00 - 100+00	RT
BELVIDERE ROAD		
180	Sta 100+00 - 109+54	LT
240	Sta 100+00 - 109+54	RT
2,460	TOTAL	

PLOT DATE = Mon Dec 03 11:17:37 2007  
 FILE NAME = c:\projects\2007\11\03\110707.dwg  
 PLOT SCALE = 50.0000 / 1 IN.  
 REFERENCE = SHEET#