40600745 POLYMERIZED LEVELING BINDER (HAND METHOD), N90

TON	LOCATION
	IL 173
6	As Needed & Directed by the Resident
6	TOTAL

40600895 CONSTRUCTING TEST STRIP

EACH	LOCATION
	IL 173
1	As Directed by the Resident
1	TOTAL

40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

SQ YD 80% FED / 20% STATE	SQ YD 90% FED / 10% STATE	LOCATION
		IL 173
144.4		Sta 230+74 - 231+24
	144.4	Sta 259+63 - 260+13
		ARGYLE ROAD
	132.4	Sta 92+99 - 93+49
		BELVIDERE ROAD
	133.9	Sta 109+04 - 109+54
144.4	410.7	SUB-TOTAL
	555.1	TOTAL

40600990 TEMPORARY RAMP

SQ YD 80% FED / 20% STATE	SQ YD 90% FED / 10% STATE	LOCATION		
		IL 173		
21.7		Sta 230+74	(26' X 7.5)	
	21.7	Sta 259+63	(26' X 7.5)	
	93.5	Sta 242+50	(24' X 35')	Stage 3 - Temporary Taper 1'' - 10'
	200.0	Sta 254+50	(24' X 75')	Stage 3 - Temporary Taper 1'' - 10'
	275.0	As Needed & Directed by the Resident (For Staging)		
		ARGYLE ROAD		
	20.8	Sta 92+99	(25' X 7.5)	
		BELVIDERE ROAD		
	20.8	Sta 109+54	(25' X 7.5)	
21.7	631.8	SUB-TOTAL		
	653.5	TOTAL		

44000100 PAVEMENT REMOVAL

SQ YD	LOCATION
	IL 173
262.7	Sta 236+22 - 244+10 (3' Widening on RT)
317.3	Sta 250+11 - 259+63 (3' Widening on RT)
580.0	TOTAL

44004250 PAVED SHOULDER REMOVAL

SQ YD	LOCATION
	IL 173
175.1	Sta 236+22 - 244+10 (1' Shoulder Widening LT & RT)
211.6	Sta 250+11 - 259+63 (1' Shoulder Widening LT & RT)
386.7	TOTAL

44004300 PAVEMENT BREAKING

SQ YD	LOCATION
	IL 173
1,736.2	Sta 244+10 - 250+11
1,736.2	TOTAL

44201759 CLASS D PATCHES, TYPE IV, 9 INCH

SQ YD	LOCATION		
	ARGYLE ROAD		
138.9	Sta 98+88 - 99+38	(50' x 25')	
	BELVIDERE ROAD		
166.7	Sta 104+74 - 105+34	(60' x 25')	
305.6	TOTAL		

44300200 STRIP REFLECTIVE CRACK CONTROL TREATMENT

FOOT	LOCATION	
	IL 173	
628	Sta 236+22 - 242+50	9' LT
628	Sta 236+22 - 242+50	9' RT
115	Sta 242+50 - 243+65	9' LT
115	Sta 242+50 - 243+65	9' RT
838	Sta 251+25 - 259+63	9' LT
838	Sta 251+25 - 259+63	9' RT
	ARGYLE ROAD	
411	Sta 93+49 - 97+60	12' LT
411	Sta 93+49 - 97+60	12' RT
57	Sta 97+60 - 98+17	12' LT
57	Sta 97+60 - 98+17	12' RT
154	Sta 98+17 - 99+71	12' LT
154	Sta 98+17 - 99+71	12' RT
	BELVIDERE ROAD	
150	Sta 100+14 - 101+64	12' LT
150	Sta 100+14 - 101+64	12' RT
106	Sta 101+64 - 102+70	12' LT
106	Sta 101+64 - 102+70	12' RT
634	Sta 102+70 - 109+04	12' LT
634	Sta 102+70 - 109+04	12' RT
6,186	TOTAL	

48100100 AGGREGATE SHOULDERS, TYPE A

TON	LOCATION				
	ARGYLE ROAD				
7.6	Sta	93+49 -	93+99	LT	(3' Wide by 8'' deep)
7.6	Sta	93+49 -	93+99	RT	(3' Wide by 8'' deep)
105.8	Sta	93+99 -	98+17	LT	(5' Wide by 8'' deep)
119.2	Sta	93+99 -	98+70	RT	(5' Wide by 8'' deep)
	BELVIDERE ROAD				
183.2	Sta	101+30 -	108+54	LT	(5' Wide by 8'' deep)
174.6	Sta	101+64 -	108+54	RT	(5' Wide by 8'' deep)
7.6	Sta	108+54 -	109+04	LT	(3' Wide by 8'' deep)
7.6	Sta	108+54 -	109+04	RT	(3' Wide by 8'' deep)
613.2	TOTAL				

48101200 AGGREGATE SHOULDERS, TYPE B

TON 80% FED / 20% STATE	TON 90% FED / 10% STATE	LOCATION				
		IL 173				
152.6		Sta	230+74 -	236+22	LT & RT	(See Typical)
	3.8	Sta	259+63 -	260+13	LT & RT	(3' Aggregate Wedge)
		ARGYLE ROAD				
	4.3	Sta	92+99 -	93+49	LT & RT	(3' Aggregate Wedge)
		BELVIDERE ROAD				
	4.7	Sta	109+04 -	109+54	LT & RT	(3' Aggregate Wedge)
	5.2	Sta	109+04 -	109+54	LT & RT	(3' Aggregate Wedge)
152.6	18.0	SUB-TOTAL				
	170.6	TOTAL				

50100300 REMOVAL OF EXISTING STRUCTURE NO. 1

EACH	LOCATION		
	IL 173		
1	Sta	244+87	(4' X 1.5' RC CULVERT)
1	TOTAL		

50100400 REMOVAL OF EXISTING STRUCTURE NO. 2

EACH	LOCATION		
	ARGYLE ROAD		
1	Sta	99+26	(1.5' X 2' RC CULVERT)
1	TOTAL		

50100500 REMOVAL OF EXISTING STRUCTURE NO. 3

EACH	LOCATION		
	BELVIDERE ROAD		
1	Sta	104+93	(3' X 2' RC CULVERT)
1	TOTAL		

PLOT DATE = Mon Dec 03 11:17:37 2007
FILE NAME = c:\pw_work\c20787\d89787cvr.dgn
PLOT SCALE = 50.000 ' / IN.
REFERENCE = REF