

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*303	129M&TS	WINNEBAGO	110	21
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

50105200 REMOVE EXISTING CULVERTS

EACH	LOCATION
1	IL 173 Sta 238+ 39 FE - LT
1	TOTAL

54214299 END SECTIONS, EQUIVALENT ROUND-SIZE 24"

EACH	LOCATION
2	BELVIDERE ROAD Sta 102+ 57.85 FE - RT
2	TOTAL

61100500 EXPLORATION TRENCH 52" DEPTH

FOOT	LOCATION
200	IL 173 As Needed & Directed by the Resident ARGYLE ROAD
50	As Needed & Directed by the Resident BELVIDERE ROAD
100	As Needed & Directed by the Resident
350	TOTAL

51500100 NAME PLATES

EACH	LOCATION
1	IL 173 Sta 244+ 47.5 BELVIDERE ROAD
1	Sta 104+ 93
2	TOTAL

54213669 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"

EACH	LOCATION
2	ARGYLE ROAD Sta 99+ 00 LT & RT
2	TOTAL

61133100 FIELD TILE JUNCTION VAULTS, 2' DIA.

EACH	LOCATION
2	IL 173 See Field Tile Drainage Detail ARGYLE ROAD
1	As Needed & Directed by the Resident BELVIDERE ROAD
2	See Field Tile Drainage Detail
5	TOTAL

54010602 PRECAST CONCRETE BOX CULVERT 6' X 2'

FOOT	LOCATION
144	BELVIDERE ROAD Sta 104+ 93 (2 CELL @ 72')
144	TOTAL

60500040 REMOVING MANHOLES

EACH	LOCATION
1	IL 173 Sta 244+ 22 RT
1	TOTAL

61140000 STORM SEWERS, SPECIAL 8"

FOOT	LOCATION
25	ARGYLE ROAD As Needed & Directed by the Resident BELVIDERE ROAD
130	See Field Tile Drainage Detail
155	TOTAL

54010702 PRECAST CONCRETE BOX CULVERT 7' X 2'

FOOT	LOCATION
180	IL 173 Sta 244+ 47.5 (2 CELL @ 90')
180	TOTAL

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

FOOT	LOCATION
168.7	IL 173 Sta 246+ 54 - 247+ 87 LT
139.3	Sta 247+ 35 - 248+ 39 RT
308.0	TOTAL

61140100 STORM SEWERS, SPECIAL 10"

FOOT	LOCATION
25	IL 173 As Needed & Directed by the Resident BELVIDERE ROAD
25	As Needed & Directed by the Resident
50	TOTAL

542A1069 PIPE CULVERTS, CLASS A, TYPE 2 24"

FOOT	LOCATION
86	ARGYLE ROAD Sta 99+ 00
86	TOTAL

60608600 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06

FOOT	LOCATION
18.7	IL 173 Sta 99+ 39 - 99+ 53 RT - Island
91.1	Sta 101+ 33 - 101+ 61 LT - Island
109.8	TOTAL

61140200 STORM SEWERS, SPECIAL 12"

FOOT	LOCATION
227	IL 173 See Field Tile Drainage Detail
227	TOTAL

542D0220 PIPE CULVERTS, CLASS D, TYPE 1 15"

FOOT	LOCATION
96	IL 173 Sta 244+ 87 RT (Stage 2 - 2 Pipe at 48')
96	TOTAL

60610400 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24

FOOT	LOCATION
17.6	ARGYLE ROAD Sta 99+ 53 RT - Island
17.6	TOTAL

63500105 DELINATORS

EACH	LOCATION
1	IL 173 Sta 244+ 35 RT
1	Sta 244+ 57 LT
2	ARGYLE ROAD Sta 99+ 00 LT & RT
2	BELVIDERE ROAD Sta 104+ 93 LT & RT
6	TOTAL

542D5479 PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 24"

FOOT	LOCATION
40	BELVIDERE ROAD Sta 102+ 57.85 FE - RT
40	TOTAL

60618300 CONCRETE MEDIAN SURFACE, 4 INCH

SQ FT	LOCATION
66.0	ARGYLE ROAD Sta 99+ 39 - 99+ 53 RT - Island
449.3	BELVIDERE ROAD Sta 101+ 33 - 101+ 61 LT - Island
515.3	TOTAL

PLOT DATE = Mon Dec 03 11:17:37 2007
 FILE NAME = c:\projects\2007\12\11\121117\121117.dgn
 PLOT SCALE = 50.0000 / 1 IN.
 REFERENCE = NONE