

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5564	111PM	WHITESIDE	16	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNITS	Total Quantity	90 % Fed. 10 % State I 000-2A URBAN
40600990	TEMPORARY RAMP	SQ YD	150	150
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	292	292
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	3,458	3,458
67100100	MOBILIZATION	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,904	1,904
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	791	791
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	309	309
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS <sup>AND</sup> SYMBOLS	SQ FT	390	390
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,051	7,051
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	448	448
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	679	679
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	214	214
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,327	1,327
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	170	170
+ 85700505	FULL-ACTUATED CONTROLLER IN EXISTING CABINET, SPECIAL	EACH	1	1
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, No. 18, 3PRR	FOOT	617	617
+ 88600400	DETECTOR LOOP, SPECIAL	FOOT	509	509
+ X0962500	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1	1
+ X8850106	INDUCTIVE LOOP DETECTOR, RACK MOUNTED	EACH	4	4
* SPECIALTY ITEMS				
+ NON- PARTICIPATING ITEMS				

PLOT DATE = Thu Dec 06 09:05:37 2007  
 FILE NAME = s:\projects\10281967\10281967.dgn  
 USER NAME = hennicke