

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326		LIVINGSTON	354	25
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*(123,123)RS-3, (124)RS-5, (123)BR-3				

**ITEM NO. 70301000 WORK ZONE PAVEMENT MARKING REMOVAL**

CONSIST OF REMOVING THE SHORT-TERM & TEMPORARY PAVEMENT MARKING QUANTITIES.

DESCRIPTION	SQ. FT.
REMOVAL OF SHORT-TERM PAVEMENT MARKINGS	4,985
REMOVAL OF TEMPORARY PAVEMENT MARKINGS IF USED BEFORE PERMANENT STRIPES PLACED	43,916
REMOVAL OF STAGING PAVEMENT MARKINGS	7,133
<b>TOTAL</b>	<b>= 56,034</b>

**ITEM NO. 70400100 TEMPORARY CONCRETE BARRIER**

LOCATION	STAGE	FOOT
STA. 835+38 TO STA. 838+57	I	320
RT. STA. 836+78 TO STA. 837+18	II	40
STA. 943+90 TO STA. 953+90	I	1000
STA. 1214+49 TO STA. 1217+68	I	320
RT. STA. 1215+89 TO STA. 1216+29	II	40
STA. 1245+05 TO STA. 1246+64	I	160
<b>TOTAL</b>		<b>= 1880</b>

**ITEM NO. 70400200 RELOCATE TEMPORARY CONCRETE BARRIER**

LOCATION	FOOT
STA. 835+38 TO STA. 838+57	320
STA. 943+90 TO STA. 953+90	1000
STA. 1214+49 TO STA. 1217+68	320
STA. 1245+05 TO STA. 1246+64	160
<b>TOTAL</b>	<b>= 1800</b>

**ITEM NO. 78100100 RAISED REFLECTIVE PAVEMENT MARKER**

LOCATION	ONE-WAY AMBER EACH	TWO-WAY AMBER EACH	ONE-WAY CRYSTAL EACH
STA. 767+72 TO STA. 803+65.4 BRIDGE	--	45	--
STA. 803+65.4 TO STA. 947+99 BRIDGE	--	180	--
STA. 947+99 TO STA. 1235+15	--	359	--
STA. 1235+15 TO STA. 1253+42 (LT. -TURN-SEE STD. 781001)	34	30	3
STA. 1253+42 TO STA. 1273+30	--	25	--
<b>SUBTOTAL</b>	<b>34</b>	<b>639</b>	<b>3</b>
<b>TOTAL</b>		<b>= 676</b>	

**ITEM NO. 78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)**

LOCATION	TWO-WAY AMBER EACH
STA. 803+65.4 TO STA. 805+91.3	3
STA. 947+99 TO STA. 950+51	3
<b>TOTAL</b>	<b>= 6</b>

**ITEM NO. 78200410 GUARDRAIL MARKERS, TYPE A**

(MONODIRECTIONAL SILVER)

LOCATION	EACH
LT. STA. 802+12.31 TO STA. 803+92.96	4
RT. STA. 801+19.91 TO STA. 804+13.06	4
LT. STA. 805+43.56 TO STA. 808+36.71	4
RT. STA. 805+63.12 TO STA. 807+43.77	4
LT. STA. 823+00.00 TO STA. 829+00.00	8
RT. STA. 813+87.50 TO STA. 838+37.50	14
LT. STA. 944+48.35 TO STA. 948+29.00	4
RT. STA. 944+73.35 TO STA. 948+29.00	4
LT. STA. 950+21.00 TO STA. 952+64.15	4
RT. STA. 950+21.00 TO STA. 951+76.65	4
<b>TOTAL</b>	<b>= 54</b>

**ITEM NO. 78200530 BARRIER WALL MARKERS, TYPE C**

TEMPORARY CONCRETE BARRIER (STAGING PLANS) (BASED ON STD. 701321-2 MARKERS EVERY 25' BI-DIRECTIONAL CRYSTAL

LOCATION	EACH
STA. 835+38 TO STA. 838+57	26
RT. STA. 836+78 TO STA. 837+18	4
STA. 943+90 TO STA. 953+90	80
STA. 1214+49 TO STA. 1217+68	26
RT. STA. 1215+89 TO STA. 1216+29	4
STA. 1245+05 TO STA. 1246+64	12
STRUCTURE 053-0179 @ STA. 949+25	4
(MONO-DIRECTIONAL CRSTAL STD. 635011)	
<b>TOTAL</b>	<b>= 156</b>

**ITEM NO. 78201000 TERMINAL MARKER-DIRECT APPLIED**

LOCATION	EACH
LT. 802+12.31	1
RT. 801+19.91	1
LT. 808+36.71	1
RT. 807+43.77	1
LT. 823+00.00	1
LT. 829+00.00	1
RT. 813+87.50	1
RT. 838+37.50	1
LT. 944+48.35	1
RT. 944+73.35	1
LT. 952+64.15	1
RT. 951+76.65	1
<b>TOTAL</b>	<b>= 12</b>

**ITEM NO. 78300100 PAVEMENT MARKING REMOVAL**

(REMOVAL OF EXISTING PAVEMENT MARKINGS CONFLICTING WITH STAGING PLANS)

LOCATION	SQ. FT.
STA. 833+50 TO STA. 840+50	555
STA. 942+00 TO STA. 955+80	1093
STA. 1212+70 TO STA. 1219+60	546
STA. 1240+55 TO STA. 1248+50	629
<b>TOTAL</b>	<b>= 2823</b>

**ITEM NO. 78300200 RAISED REFLECTIVE PAVEMENT MAKER REMOVAL**

LOCATION	EACH
STA. 767+72 TO STA. 1273+30	632
<b>TOTAL</b>	<b>= 632</b>

**ITEM NO. X0323265 REMOVE EXISTING RIPRAP**

LOCATION	SQ. YD.
LT. STA. 856+20	20
RT. STA. 1061+37	25
LT. STA. 1118+10	16
LT. STA. 1216+10	50
<b>TOTAL</b>	<b>= 111</b>

**ITEM NO. X0323988 TEMPORARY SOIL RETENTION SYSTEM**

LOCATION	SQ. FT.
STA. 836+98 (STAGE I & II)	150
STA. 1216+09 (STAGE I & II)	145
STA. 1245+85 (STAGE I & II)	130
<b>TOTAL</b>	<b>= 425</b>

**ITEM NO. X0324762 WIDE LOAD DETOUR SIGNING**

LOCATION	L SUM
STA. 949+25 (SN 053-0050)	1
STA. 1245+85 (DBL. 6'x2' RCBC)	

**ITEM NO. XX005374 PIPE UNDERDRAINS 6" (MODIFIED)**

(QUANTITY PROVIDED BY DISTRICT)

LOCATION	FOOT
DRAINAGE EASEMENT AT STA. 1245+85	305
<b>TOTAL</b>	<b>= 305</b>

**ITEM NO. X0976500 END SECTIONS TO BE REMOVED**

CULVERT NO.	LOCATION	SIZE	TYPE	EACH
①	LT. & RT. STA. 774+90	3' x 2'	PCBC	2
②	RT. STA. 788+96	3' x 2'	PCBC	1
③	LT. & RT. STA. 810+98.5	3' x 2'	PCBC	2
⑥	LT. STA. 844+02.5	3' x 2'	PCBC	1
⑧	LT. & RT. STA. 1008+02	3' x 2'	PCBC	2
⑨	LT. & RT. STA. 1044+02	3' x 2'	PCBC	2
⑩	LT. & RT. STA. 1061+37	3' x 2'	PCBC	2
---	RT. STA. 1076+34	18"	METAL	1
---	LT. & RT. STA. 1142+35	36" ERS	CONC	2
---	LT. & RT. STA. 1171+32.5	36" ERS	CONC	2
⑬	LT. & RT. STA. 1245+20	3' x 2'	PCBC	2
<b>TOTAL</b>				<b>= 19</b>

**ITEM NO. 35501308 HOT-MIX ASPHALT BASE COURSE, 6"**

LOCATION	DESCRIPTION	SQ. YD.
RT. STA. 769+10	P. E.	44
RT. STA. 781+25	P. E.	36
LT. STA. 992+65	P. E.	38
RT. STA. 996+64	P. E.	49
LT. STA. 1000+87	P. E.	78
LT. STA. 1035+25	P. E.	36
RT. STA. 1047+37	P. E.	81
LT. STA. 1050+05	P. E.	79
LT. STA. 1091+13	P. E.	36
RT. STA. 1144+71	P. E.	36
RT. STA. 1189+78	P. E.	49
RT. STA. 1192+62.5	P. E.	40
RT. STA. 1193+87	P. E.	40
LT. STA. 1205+18	P. E.	36
RT. STA. 1231+05	P. E.	36
RT. STA. 1236+06	C. E.	28
RT. STA. 1237+47	C. E.	61
LT. STA. 1238+26	C. E.	208
LT. STA. 1240+55	C. E.	61
RT. STA. 1246+37	C. E.	47
RT. STA. 1247+09	C. E.	47
LT. STA. 1249+09	C. E.	61
RT. STA. 1250+40	C. E.	49
RT. STA. 1252+07	C. E.	28
<b>TOTAL</b>		<b>= 1304</b>

**ITEM NO. 35501320 HOT-MIX ASPHALT BASE COURSE, 9"**

LOCATION	SQ. YD.
LT. STA. 834+50 TO STA. 839+50	317
RT. STA. 834+50 TO STA. 839+50	444
LT. STA. 943+00 TO STA. 947+95	165
RT. STA. 944+90 TO STA. 947+95	102
LT. STA. 950+48 TO STA. 955+00	151
RT. STA. 950+48 TO STA. 952+90	81
RT. STA. 943+00 TO STA. 948+29	456
RT. STA. 950+21 TO STA. 955+00	300
LT. STA. 1213+50 TO STA. 1218+75	332
RT. STA. 1213+50 TO STA. 1218+75	332
LT. STA. 1240+55 TO STA. 1248+08	680
RT. STA. 1240+55 TO STA. 1248+08	653
<b>TOTAL</b>	<b>= 4013</b>

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES

△ REVISED 2/14/08

SCALE: VERT. DATE  
HORIZ. DRAWN BY CHECKED BY

schedules.dgn