

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326		LIVINGSTON	354	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
*(123,123)RS-3, (124)RS-5, (123)BR-3				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED/20% ST.		VILLAGE OF FORREST							
			TOTAL QUANTITY	MAINLINE ROADWAY I000-2A F	STRUCTURE SN 053-0179 X081-2A BRF	SFTY-2A/ SN 053-2027 F	NEW SIDEWALKS 50%STATE 50% FED.					
54214293	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	2	2								
54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	4	4								
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24'	EACH	4	4								
54214521	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36"	EACH	12	12								
54248510	CONCRETE COLLAR	CU YD	1.2	1.2								
*56400500	FIRE HYDRANTS TO BE REMOVED	EACH	3	3								
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	68		68							
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	11.9	11.9								
60100935	PIPE DRAINS 10"	FOOT	70	70								
60100945	PIPE DRAINS 12"	FOOT	50	50								
60100955	PIPE DRAINS 15"	FOOT	40	40								
60100965	PIPE DRAINS 18"	FOOT	50	50								
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	148		148							
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1								
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2								
60255500	MANHOLES TO BE ADJUSTED	EACH	8	8								
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1								
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	62	62								
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	89000	89000								
61100605	MISCELLANEOUS CONCRETE	CU YD	6.9	6.9								
61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	250	250								
61101011	STORM SEWERS PROTECTED, CLASS A, 10"	FOOT	250	250								
61101013	STORM SEWERS PROTECTED, CLASS A, 12"	FOOT	250	250								
61101016	STORM SEWERS PROTECTED, CLASS A, 14"	FOOT	250	250								
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	15	15								
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	20	20								
61139900	STORM SEWERS (SPECIAL) 6"	FOOT	300	300								
61140000	STORM SEWERS (SPECIAL) 8"	FOOT	300	300								
61140100	STORM SEWERS (SPECIAL) 10"	FOOT	300	300								
61140200	STORM SEWERS, SPECIAL 12"	FOOT	300	300								
61140300	STORM SEWERS, SPECIAL 14"	FOOT	300	300								

LEGEND:
 * SPECIALTY ITEMS
 *** SFTY - 3N
 + NON-PARTICIPATING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES
 SHEET 5 OF 7**

SCALE: VERT. NONE
 HORIZ. NONE
 DATE:

DRAWN BY:
 CHECKED BY:

\$\$\$\$\$FILENAME\$\$\$\$\$
 \$\$\$DATE\$\$\$