

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	*	LIVINGSTON	354	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*(123,123)RS-3, (124)RS-5, (123)BR-3				

**ITEM NO. 42400100 PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH**

(AREAS MEASURED BY MICROSTATION)  
\*SEE DISTRICT DETAILS (ADA SIDEWALK ACCESSIBILITY RAMPS)

LOCATION	WIDTH	SQ. YD.
RT. STA. 1252+20 TO STA. 1254+07.5	5'	938
RT. STA. 1255+57	*METHOD 1	62
LT. STA. 1256+00	METHOD 1	77
RT. STA. 1256+00	METHOD 1	61
LT. STA. 1259+00	METHOD 1	119
RT. STA. 1259+00	METHOD 1	123
LT. STA. 1259+50	METHOD 1	130
RT. STA. 1259+50	METHOD 1	122
RT. STA. 1260+60 TO STA. 1260+98	4'	152
RT. STA. 1261+40 TO STA. 1262+00	4'	240
LT. STA. 1262+50	METHOD 1	119
RT. STA. 1262+50	METHOD 1	120
LT. STA. 1262+95	METHOD 1	61
RT. STA. 1262+95	METHOD 1	98
LT. STA. 1265+90	METHOD 1	91
RT. STA. 1265+90	METHOD 1	73
LT. STA. 1266+45	METHOD 1	57
LT. STA. 1269+95	METHOD 1	122
TOTAL = 2765		

**ITEM NO. 42400800 DETECTABLE WARNINGS**

LOCATION	SQ. YD.
RT. STA. 1255+57	10
LT. STA. 1256+00	10
RT. STA. 1256+00	10
LT. STA. 1259+00	20
RT. STA. 1259+00	20
LT. STA. 1259+50	20
RT. STA. 1259+50	20
LT. STA. 1262+50	20
RT. STA. 1262+50	20
LT. STA. 1262+95	10
RT. STA. 1262+95	10
LT. STA. 1265+90	10
RT. STA. 1265+90	10
LT. STA. 1266+45	10
LT. STA. 1269+95	20
TOTAL = 220	

**ITEM NO. 44000100 PAVEMENT REMOVAL**

LOCATION	SQ. YD.
LT. STA. 834+50 TO STA. 839+50	135
LT. STA. 1213+50 TO STA. 1218+75	138
RT. STA. 1213+50 TO STA. 1218+75	157
LT. STA. 1244+43 TO STA. 1248+08	241
RT. STA. 1244+55 TO STA. 1248+08	251
TOTAL = 922	

**ITEM NO. 44000155 HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"**

LOCATION	SQ. YD.
(MAINLINE)	
STA. 766+60 TO STA. 767+72	327
STA. 767+72 TO STA. 803+65.4	9582
BRIDGE OMISSION	
STA. 805+91.3 TO STA. 945+07	37,109
BRIDGE OMISSION	
STA. 952+62 TO STA. 1251+79	79,779
STA. 1251+79 TO STA. 1252+56.5	258
STA. 1252+56.5 TO STA. 1263+10	4214
STA. 1263+10 TO STA. 1264+39.5	519
STA. 1264+39.5 TO STA. 1265+81	568
STA. 1265+81 TO STA. 1266+66	340
STA. 1266+66 TO STA. 1268+00	535
STA. 1268+00 TO STA. 1269+20	503
STA. 1269+20 TO STA. 1270+09	356
STA. 1270+09 TO STA. 1272+65	990
STA. 1272+65 TO STA. 1273+30	260
(SIDEROADS) (AREAS MEASURED BY MICROSTATION)	
LT. & RT. 1500N	422
LT. & RT. 1300N	713
LT. & RT. 1200N	531
LT. & RT. 1100N	433
LT. & RT. 1000N	475
LT. & RT. 900N	420
RT. VAUGHN ST.	160
LT. BULLARD ST.	85
LT. & RT. NORTH ST.	148
LT. & RT. JAMES ST.	148
LT. & RT. MARTIN ST.	148
LT. & RT. WATSON ST.	139
LT. & RT. JOHN ST.	146
LT. & RT. KRACK ST.	169
TOTAL = 139,447	

**ITEM NO. 44000198 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH**

(PARKING AREAS IN FORREST)

LOCATION	AVG. WIDTH	SQ. YD.
RT. STA. 1263+11 TO RT. STA. 1265+81	10'	304
LT. STA. 1264+40 TO LT. STA. 1265+75	9'	140
RT. STA. 1266+66 TO RT. STA. 1269+21	5.5'	168
LT. STA. 1267+83 TO LT. STA. 1269+10	9.4'	138
LT. STA. 1270+09 TO LT. STA. 1272+65	10'	277
TOTAL = 1027		

**ITEM NO. 44000200 DRIVEWAY PAVEMENT REMOVAL**

(AREAS MEASURED BY MICROSTATION)

LOCATION	DESCRIPTION	SQ. YD.
LT. STA. 821+86	P.E. (BIT./CONC.)	72
LT. STA. 1000+87	P.E. (BIT.)	84
RT. STA. 1047+37	P.E. (BIT.)	64
LT. STA. 1050+05	P.E. (BIT.)	76
LT. STA. 1238+26	C.E. (BIT.)	216
LT. STA. 1240+55	C.E. (CONC.)	205
LT. STA. 1242+76	C.E. (CONC.)	149
RT. STA. 1248+25	C.E. (CONC.)	175
LT. STA. 1248+32	C.E. (CONC.)	167
RT. STA. 1249+95	C.E. (CONC.)	189
RT. STA. 1261+31	P.E. (BIT.)	57
TOTAL = 1454		

**ITEM NO. 44000500 COMBINATION CURB AND GUTTER REMOVAL**

LOCATION	FOOT
RT. STA. 1260+90 TO STA. 1261+48	58
TOTAL = 58	

**ITEM NO. 44000600 SIDEWALK REMOVAL**

(AREAS MEASURED BY MICROSTATION)

LOCATION	SQ. YD.
RT. STA. 1255+57	52
LT. STA. 1256+00	56
RT. STA. 1256+00	43
LT. STA. 1259+00	101
RT. STA. 1259+00	99
LT. STA. 1259+50	106
RT. STA. 1259+50	107
RT. STA. 1260+60 TO STA. 1262+00	506
LT. STA. 1262+50	100
RT. STA. 1262+50	106
LT. STA. 1262+95	51
RT. STA. 1262+95	94
LT. STA. 1265+90	92
RT. STA. 1265+90	119
LT. STA. 1266+45	48
LT. STA. 1269+95	119
TOTAL = 1799	

**ITEM NO. 44001700 COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT**

LOCATION	FOOT
RT. STA. 1255+57	10
LT. STA. 1256+00	10
RT. STA. 1256+00	10
LT. STA. 1259+00	18
RT. STA. 1259+00	18
LT. STA. 1259+50	19
RT. STA. 1259+50	19
LT. STA. 1262+50	19
RT. STA. 1262+50	19
LT. STA. 1262+95	10
RT. STA. 1262+95	10
LT. STA. 1265+90	9
RT. STA. 1265+90	8
LT. STA. 1266+45	10
LT. STA. 1269+95	19
TOTAL = 208	

**ITEM NO. 44004000 PAVED DITCH REMOVAL**

LOCATION	WIDTH (FOOT)	FOOT
RT. STA. 1130+00	9	55
TOTAL = 55		

**ITEM NO. 44004250 PAVED SHOULDER REMOVAL**

LOCATION	WIDTH (FOOT)	SQ. YD.
LT. & RT. STA. 767+72 TO STA. 803+65.4	1.5	1199
BRIDGE		
LT. & RT. STA. 805+91.3 TO STA. 810+16	1.5	142
LT. & RT. STA. 810+16 TO STA. 863+11	8	9413
LT. & RT. STA. 863+11 TO STA. 947+95	1.5	2828
BRIDGE		
LT. & RT. STA. 950+49 TO STA. 1252+00	1.5	10,050
LT. STA. 991+30 TO STA. 994+00	VAR.	109
RT. STA. 991+30 TO STA. 993+80	VAR.	106
TOTAL = 23,847		

**ITEM NO. 44201723 CLASS D PATCHES, TYPE IV, 6 INCH**

LOCATION	DESCRIPTION	LENGTH (FOOT)	WIDTH (FOOT)	SQ. YD.
RT. STA. 1243+06	PIPE CULV. REM.	37.5	6.75	28
RT. STA. 1243+06	PIPE CULV.	30	6.75	23
TOTAL = 51				

**ITEM NO. 44201839 CLASS D PATCHES, TYPE II, 16 INCH**

LOCATION	DESCRIPTION	LENGTH (FOOT)	WIDTH (FOOT)	SQ. YD.
RT. STA. 783+95 TO STA. 784+05	PAVEMENT PATCH	10	12	14
LT. STA. 783+97 TO STA. 784+03	PAVEMENT PATCH	6	12	8
RT. STA. 792+76 TO STA. 792+84	PAVEMENT PATCH	8	12	11
LT. STA. 792+76 TO STA. 792+84	PAVEMENT PATCH	8	12	11
RT. STA. 794+76 TO STA. 794+84	PAVEMENT PATCH	8	12	11
LT. STA. 794+76 TO STA. 794+84	PAVEMENT PATCH	8	12	11
RT. STA. 803+15 TO STA. 803+25	PAVEMENT PATCH	10	12	14
LT. STA. 814+35 TO STA. 814+45	PAVEMENT PATCH	10	12	14
RT. STA. 817+16 TO STA. 817+24	PAVEMENT PATCH	8	12	11
LT. STA. 817+16 TO STA. 817+24	PAVEMENT PATCH	8	12	11
RT. STA. 820+36 TO STA. 820+44	PAVEMENT PATCH	8	12	11
LT. STA. 820+36 TO STA. 820+44	PAVEMENT PATCH	8	12	11
RT. STA. 837+97 TO STA. 838+03	PAVEMENT PATCH	6	12	8
LT. STA. 837+97 TO STA. 838+03	PAVEMENT PATCH	6	12	8
RT. STA. 843+15 TO STA. 843+25	PAVEMENT PATCH	10	12	14
LT. STA. 843+15 TO STA. 843+25	PAVEMENT PATCH	10	12	14
LT. STA. 852+46 TO STA. 852+54	PAVEMENT PATCH	8	12	11
RT. STA. 861+96 TO STA. 862+04	PAVEMENT PATCH	8	12	11
LT. STA. 870+97 TO STA. 871+03	PAVEMENT PATCH	6	12	8
RT. STA. 888+96 TO STA. 889+04	PAVEMENT PATCH	8	12	11
LT. STA. 888+96 TO STA. 889+04	PAVEMENT PATCH	8	12	11
RT. STA. 888+95 TO STA. 889+05	PAVEMENT PATCH	10	12	14
LT. STA. 888+95 TO STA. 889+05	PAVEMENT PATCH	6	12	8
RT. STA. 922+97 TO STA. 923+03	PAVEMENT PATCH	6	12	8
LT. STA. 922+97 TO STA. 923+03	PAVEMENT PATCH	6	12	8
RT. STA. 924+27 TO STA. 924+33	PAVEMENT PATCH	6	12	8
LT. STA. 924+27 TO STA. 924+33	PAVEMENT PATCH	6	12	8
RT. STA. 947+95 TO STA. 948+05	PAVEMENT PATCH	10	12	14
LT. STA. 947+95 TO STA. 948+05	PAVEMENT PATCH	10	12	14
RT. STA. 953+67 TO STA. 953+73	PAVEMENT PATCH	6	12	8
LT. STA. 953+67 TO STA. 953+73	PAVEMENT PATCH	6	12	8
RT. STA. 961+95 TO STA. 962+05	PAVEMENT PATCH	10	12	14
LT. STA. 961+95 TO STA. 962+05	PAVEMENT PATCH	10	12	14
RT. STA. 970+95 TO STA. 971+05	PAVEMENT PATCH	10	12	14
LT. STA. 970+95 TO STA. 971+05	PAVEMENT PATCH	6	12	8
RT. STA. 990+46 TO STA. 990+54	PAVEMENT PATCH	8	12	11
LT. STA. 1000+46 TO STA. 1000+54	PAVEMENT PATCH	8	12	11
RT. STA. 1004+96 TO STA. 1005+04	PAVEMENT PATCH	8	12	11
LT. STA. 1006+97 TO STA. 1007+03	PAVEMENT PATCH	6	12	8
RT. STA. 1006+97 TO STA. 1007+03	PAVEMENT PATCH	6	12	8
LT. STA. 1045+97 TO STA. 1046+03	PAVEMENT PATCH	6	12	8
RT. STA. 1045+97 TO STA. 1046+03	PAVEMENT PATCH	6	12	8
RT. STA. 1054+96 TO STA. 1055+04	PAVEMENT PATCH	8	12	11
LT. STA. 1089+97 TO STA. 1090+03	PAVEMENT PATCH	6	12	8
RT. STA. 1089+97 TO STA. 1090+03	PAVEMENT PATCH	6	12	8
LT. STA. 1090+46 TO STA. 1090+54	PAVEMENT PATCH	6	12	8
RT. STA. 1090+46 TO STA. 1090+54	PAVEMENT PATCH	6	12	8
LT. STA. 1104+95 TO STA. 1105+05	PAVEMENT PATCH	10	12	14
RT. STA. 1107+97 TO STA. 1108+03	PAVEMENT PATCH	6	12	8
LT. STA. 1107+97 TO STA. 1108+03	PAVEMENT PATCH	6	12	8
RT. STA. 1127+96 TO STA. 1128+04	PAVEMENT PATCH	8	12	11
LT. STA. 1129+46 TO STA. 1129+54	PAVEMENT PATCH	8	12	11
RT. STA. 1129+46 TO STA. 1129+54	PAVEMENT PATCH	8	12	11
LT. STA. 1132+96 TO STA. 1133+04	PAVEMENT PATCH	8	12	11
RT. STA. 1132+96 TO STA. 1133+04	PAVEMENT PATCH	8	12	11
LT. STA. 1156+97 TO STA. 1157+03	PAVEMENT PATCH	6	12	8
RT. STA. 1156+97 TO STA. 1157+03	PAVEMENT PATCH	6	12	8
LT. STA. 1160+45 TO STA. 1160+55	PAVEMENT PATCH	10	12	14
RT. STA. 1160+45 TO STA. 1160+55	PAVEMENT PATCH	8	12	11
LT. STA. 1161+47 TO STA. 1161+53	PAVEMENT PATCH	6	12	8
RT. STA. 1161+47 TO STA. 1161+53	PAVEMENT PATCH	6	12	8
LT. STA. 1161+97 TO STA. 1162+03	PAVEMENT PATCH	6	12	8
RT. STA. 1161+97 TO STA. 1162+03	PAVEMENT PATCH	10	12	14
LT. STA. 1182+45 TO STA. 1182+55	PAVEMENT PATCH	10	12	14
RT. STA. 1182+45 TO STA. 1182+55	PAVEMENT PATCH	8	12	11
LT. STA. 1193+97 TO STA. 1194+03	PAVEMENT PATCH	6	12	8
RT. STA. 1193+97 TO STA. 1194+03	PAVEMENT PATCH	8	12	11
LT. STA. 1206+96 TO STA. 1207+04	PAVEMENT PATCH	8	12	11
RT. STA. 1232+96 TO STA. 1233+04	PAVEMENT PATCH	8	12	11
LT. STA. 1232+96 TO STA. 1233+04	PAVEMENT PATCH	8	12	11
RT. STA. 1260+67 TO STA. 1260+73	PAVEMENT PATCH	6	12	8
LT. STA. 1260+67 TO STA. 1260+73	PAVEMENT PATCH	6	12	8
RT. STA. 1261+12 TO STA. 1261+18	PAVEMENT PATCH	6	12	8
LT. STA. 1261+12 TO STA. 1261+18	PAVEMENT PATCH	6	12	8
TOTAL = 772				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY