

RESURFACING SCHEDULE				
LOCATION	DESCRIPTION	LENGTH	CAPE SEAL	CRACK FILLING
			SQ YD	POUND
0+12 TO 73+10		7298	20019.3	350
73+10 TO 79+20		610	1626.7	29
79+20 TO 104+60		2565	8550	154
104+60 TO 105+25		65	202.2	4
105+25 TO 120+74		1549	5008.7	74
DEPUE RD S TO 29 S	CONNECTOR	386	2192	19
TOTAL			37598.9	630

PAVEMENT MARKING SCHEDULE									
LOCATION	DESCRIPTION	LENGTH	PAINT PVMT MARK		PAINT PVMT MARK	TEMP FLEX PVMT MARKERS	SHORT TERM PVMT MARKING	WORK ZONE PVMT MARK REMOVAL	RAISED REF PVMT MARKER
			WHITE 4"	YELLOW 4"	YELLOW 6"	EACH	FOOT	SQ FT	EACH
			FOOT	FOOT	FOOT				
0+12 TO 26+79		2667	5334	4319	230	133	267	89	33
26+79 TO 59+56		3277	6554	0	820	164	328	109	41
59+56 TO 72+69		1313	2626	1862	190	66	131	44	16
72+68 TO 73+58		90	0	0	0	5	9	3	1
73+58 TO 114+05		4047	8094	8094	0	202	405	135	51
114+05 TO 114+65		60	60	0	0	3	6	2	1
114+65 TO 120+74		609	1218	1080	0	30	61	20	8
S DEPUE RD TO S 29	CONNECTOR	386	834	772	0	19	39	13	5
SUBTOTAL			24720	16127					
TOTAL			40847	1240	622	1246	415	156	

NOTE: NO PASSING ZONES SHALL BE REPLACED