

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
626	(42B)1	KNOX	11	2
STA. 396+95.50		TO STA. 397+28.50		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

COMMITMENTS

No commitments have been made for this project.

GENERAL NOTES

Plan dimensions and details relative to existing structure have been taken from existing plans and are subject to nominal construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

Construction field requirements for any guardrail work shall be according to Article 633 of the "Standard Specifications for Road and Bridge Construction". Guardrail may be removed & re-erected at the Contractor's discretion for materials delivery and equipment access but shall be included in the cost of the contract. Any structure or guardrail damage that occurs as a result of construction activities shall be the responsibility of the Contractor and repaired and/or replaced without additional cost to the Department.

Construction field requirements for Erosion Control Blanket work shall be according to Supplemental Specification for Section 1081.

Onsite storage of metal materials shall be off of the pavement and according to Article 1006.34

PLOT DATE : #DATE#-13-07
 FILE NAME : #FILE#S:\GEN\DRAP\T\STD\PLNS\SQUAD\A\BRIDGE\Contracta\Emergency\PCB\Bund\Repairs\6B761_S1048-0014_IL_47over-the-Crk.dgn
 PLOT SCALE : #SCALE#
 REFERENCE : #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

SCALE: VERT.
 HORIZ.
 DATE 08-13-2007

DRAWN BY CEJ
 CHECKED BY