

SUMMARY OF QUANTITIES			80% FEDERAL 20% STATE CONSTRUCTION CODE X080-2A
CODE NO.	ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	100
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	13
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	160
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	55
48101200	AGGREGATE SHOULDERS, TYPE B	TON	44
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	3.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	4.6
50300260	BRIDGE DECK GROOVING	SQ YD	174
50300300	PROTECTIVE COAT	SQ YD	185
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	1611
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2920
• 50901050	STEEL RAILINGS, TYPE SM	FOOT	104
51500100	NAME PLATES	EACH	1
59000200	EPOXY CRACK INJECTION	FOOT	5
• 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	190
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	28
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	10
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	640
• 78200420	GUARDRAIL MARKERS, TYPE B	EACH	12
• 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	5
X0324865	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	265
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	3
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	179

• SPECIALTY ITEM