

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	CONSTRUCTION TYPE CODE:	UNIT	TOTAL QUANTITY	CHAMPAIGN COUNTY		VERMILION COUNTY		VERMILION COUNTY	
					RURAL		RURAL		URBAN	
					STA. 734+00.00 TO STA. 1053+06.00		STA. 1053+06.00 TO STA. 1676+10.00 STA. 1752+66.00 TO STA. 1853+50.80		STA. 1676+10.00 TO STA. 1752+66.00 STA. 1853+50.80 TO STA. 2231+13.24	
				90% FED. 10% STATE SFTY-3J	90% FED. 10% STATE SFTY-3N	90% FED. 10% STATE SFTY-3J	90% FED. 10% STATE SFTY-3N	90% FED. 10% STATE SFTY-3J	90% FED. 10% STATE SFTY-3N	
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED		EACH	79.0	13.0	0.0	24.0	0.0	42.0	0.0
* 63100217	TRAFFIC BARRIER TERMINAL, TYPE 6B(SPECIAL)		EACH	12.0	0.0	0.0	3.0	0.0	9.0	0.0
63200310	GUARDRAIL REMOVAL		FOOT	65,540.0	7,708.0	0.0	15,688.0	0.0	42,144.0	0.0
63400105	GUARD POSTS		EACH	204.0	0.0	24.0	0.0	80.0	0.0	100.0
63400205	GUARD POSTS REMOVAL		EACH	220.0	0.0	41.0	0.0	80.0	0.0	99.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A		CAL MO	5.0	0.50	0.50	1.25	1.25	0.75	0.75
67100100	MOBILIZATION		L SUM	1.0	0.10	0.10	0.25	0.25	0.15	0.15
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411		EACH	15.0	0.0	0.0	0.0	0.0	15.0	0.0
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406		L SUM	1.0	0.10	0.10	0.25	0.25	0.15	0.15
* 78200410	GUARDRAIL MARKERS, TYPE A		EACH	931.0	109.0	0.0	246.0	0.0	576.0	0.0
* 78201000	TERMINAL MARKER - DIRECT APPLIED		EACH	102.0	14.0	0.0	30.0	0.0	58.0	0.0
* X0640200	TRAFFIC BARRIER TERMINAL (SPECIAL)		EACH	2.0	0.0	0.0	0.0	0.0	2.0	0.0
X0931400	INLET BOXES TO BE ADJUSTED (SPECIAL)		EACH	1.0	0.0	0.0	0.0	0.0	0.0	1.0
X6050700	REMOVE INLET BOX		EACH	2.0	0.0	0.0	0.0	2.0	0.0	0.0
* X6311215	TRAFFIC BARRIER TERMINAL (C-A-T)		EACH	2.0	0.0	0.0	0.0	0.0	0.0	2.0
X6333500	TRAFFIC BARRIER TERMINAL REMOVAL		EACH	2.0	0.0	0.0	0.0	0.0	0.0	2.0
X7015005	CHANGEABLE MESSAGE SIGN		CAL DA	28.0	5.6	0.0	7.0	7.0	4.2	4.2
50300225	CONCRETE STRUCTURES		CU YD	276.6	29.9	15.0	53.4	26.7	75.8	75.8
Z0013300	CONCRETE REMOVAL (SPECIAL)		SQ YD	1,421.0	0.0	197.3	0.0	551.7	0.0	672.0
* Z0026260	FURNISHING AND INSTALLING TUBULAR THRIE BEAM		FOOT	191.0	0.0	0.0	25.0	0.0	166.0	0.0
* Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3		EACH	51.0	0.0	6.0	0.0	20.0	0.0	25.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE		L SUM	1.0	0.10	0.10	0.25	0.25	0.15	0.15
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED		EACH	790.0	0.0	93.0	0.0	327.0	0.0	370.0

*SPECIALTY ITEMS

▲ REVISIED 2/27/08

FILE NAME = c:\projects\4501407 (v8)\70643_text.dgn	USER NAME = eollierbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. 74	SECTION FY08HSIP	COUNTY --	TOTAL SHEETS 172	SHEET NO. 7	
PLOT SCALE = 40.0000' / IN.								70643			
PLOT DATE = 12/20/2007								FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			