

SCHEDULE OF QUANTITIES

SEEDING SCHEDULE										
STRUCTURE NO.	STATION	TO	STATION	DESCRIPTION	SEEDING CLASS 2A 25000210.000	NITROGEN FERTILIZER NUTRIENTS 25000400	PHOSPHORUS FERTILIZER NUTRIENTS 25000500	POTASSIUM FERTILIZER NUTRIENTS 25000600	MULCH METHOD 2 25100115	TEMPORARY EROSION CONTROL SEEDING 28000250
					ACRE	POUND	POUND	POUND	ACRE	POUND
092-0084	2000+75.00		2002+25.00	IMPACT ATTENUATOR	0.110	9.9	9.9	9.9	0.110	11.0
	2003+61.20		2004+36.20	WIDENING FOR TYPE 1 TERMINAL	0.017	1.5	1.5	1.5	0.017	1.7
EMBANKMENT AT 2007+00 BOWMAN AVE. RAMP	2009+07.50		2009+82.50	WIDENING FOR TYPE 1 TERMINAL	0.017	1.5	1.5	1.5	0.017	1.7
	8+61.14		9+36.14		0.017	1.5	1.5	1.5	0.017	1.7
092-0198	2009+00.00		2011+50.00	IMPACT ATTENUATOR	0.184	16.5	16.5	16.5	0.184	18.4
092-0016	2024+62.00		2025+46.00	WIDENING FOR TYPE 1 TERMINAL	0.000	0.0	0.0	0.0	0.000	0.0
	2028+50.00		2029+34.00	WIDENING FOR TYPE 1 TERMINAL	0.024	2.2	2.2	2.2	0.024	2.4
092-0019	2042+42.00		2043+15.00	WIDENING FOR TYPE 1 TERMINAL	0.021	1.9	1.9	1.9	0.021	2.1
	2053+55.00		2054+27.00	WIDENING FOR TYPE 1 TERMINAL	0.020	1.8	1.8	1.8	0.020	2.0
092-2001	2076+04.00		2076+88.00	WIDENING FOR TYPE 1 TERMINAL	0.093	8.4	8.4	8.4	0.093	9.3
	2098+38.00		2099+22.00	WIDENING FOR TYPE 1 TERMINAL	0.022	1.9	1.9	1.9	0.022	2.2
092-0151	2139+00.00		2141+50.00	IMPACT ATTENUATOR	0.184	16.5	16.5	16.5	0.184	18.4
	2136+72.00		2137+45.00	WIDENING FOR TYPE 1 TERMINAL	0.022	2.0	2.0	2.0	0.022	2.2
	2143+04.00		2143+77.00	WIDENING FOR TYPE 1 TERMINAL	0.031	2.8	2.8	2.8	0.031	3.1
092-0022	2152+75.00		2155+50.00	IMPACT ATTENUATOR	0.202	18.2	18.2	18.2	0.202	20.2
	2149+73.00		2150+46.00	WIDENING FOR TYPE 1 TERMINAL	0.015	1.3	1.3	1.3	0.015	1.5
	2156+23.00		2156+96.00	WIDENING FOR TYPE 1 TERMINAL	0.033	2.9	2.9	2.9	0.033	3.3
092-0024	2192+25.00		2192+98.00	WIDENING FOR TYPE 1 TERMINAL	0.034	3.0	3.0	3.0	0.034	3.4
	2198+53.00		2199+25.00	WIDENING FOR TYPE 1 TERMINAL	0.017	1.5	1.5	1.5	0.017	1.7
092-0026	2209+62.00		2210+35.00	WIDENING FOR TYPE 1 TERMINAL	0.022	2.0	2.0	2.0	0.022	2.2
LYNCH RD. RAMP	12+50.00		13+25.00	WIDENING FOR TYPE 1 TERMINAL	0.017	1.5	1.5	1.5	0.017	1.7
092-0023	2207+94.00		2208+67.00	WIDENING FOR TYPE 1 TERMINAL	0.028	2.6	2.6	2.6	0.028	2.8
092-0025	2217+84.00		2218+57.00	WIDENING FOR TYPE 1 TERMINAL	0.024	2.1	2.1	2.1	0.024	2.4
	2217+08.00		2217+80.00	WIDENING FOR TYPE 1 TERMINAL	0.016	1.5	1.5	1.5	0.016	1.6
TOTAL =					6.305	567.5	567.5	567.5	6.305	630.5
USE =					6.5	568.0	568.0	568.0	6.5	631.0

**CHAMPAIGN & VERMILION

FILE NAME = c:\projects\d501407 (v8)\70643_text.dgn	USER NAME = collierbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			74	FY08HSIP	**	172	20	
		PLOT SCALE = 40.0000' / IN.	CHECKED -			SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	70643
		PLOT DATE = 12/20/2007	DATE -								FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT