



TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED

STEEL PLATE BEAM GUARDRAIL, TYPE A

IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3 - 2.0 EACH

SAND MODULE IMPACT ATTENUATORS TO BE REMOVED - 38.0 EACH

CONCRETE REMOVAL SPECIAL (E) = 48.0 SQYD, (W) = 44.9 SQYD

***** CRASHWALLS TO BE EXTENDED

NOTE:
PIPE UNDERDRAINS 4" (SPECIAL) SHALL BE EXTENDED TO THE FLOW LINE OR NEAREST INLET. RESETTING OR REPLACING THE PIPE UNDERDRAIN HEADWALLS SHALL BE INCIDENTAL TO PIPE UNDERDRAINS 4".

TRAFFIC BARRIER TERMINALS, TYPE 1 (SPECIAL) FLARED SHALL BE FLARED TO 4'-0" OFFSET FROM THE EDGE OF SHOULDER TO ACHIEVE THE DESIRED LENGTH OF NEED PER STANDARD 630301.

SEC.7, R11E, T19N, 3RD PM

SEC.7, R14W, T19N, 2ND PM

| | | | |
|--|-----------------------|------------|-----------|
| FILE NAME = | USER NAME = collierbw | DESIGNED - | REVISED - |
| ct:\projects\d501407 (v8)\70643.plnsheet.dgn | | DRAWN - | REVISED - |
| | | CHECKED - | REVISED - |
| | | DATE - | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

I-74 GUARDRAIL & IMPACT ATTENUATORS

SCALE: 1:40 SHEET NO. OF SHEETS STA. 896+00 TO STA. 907+00

| | | | | |
|--|----------|--------|--------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 74 | FY08HSIP | ** | 172 | 29 |
| CONTRACT NO. 70643 | | | | |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | | |

** CHAMPAIGN & VERMILION COUNTIES