

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAI 74 FAI 74
 RURAL RURAL
 STA. 1035+00
 TO 1043+00
 90% FED / 10% STATE 90% FED / 10% STATE
 STR# STR#
 057-0125(EB) 057-0126(WB)
 X071-2A SFTY-2A

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
20400800	FURNISHED EXCAVATION	CU YD	20.0	20.0	0.0
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	82.4	82.4	0.0
25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5	0.0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45.0	45.0	0.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45.0	45.0	0.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45.0	45.0	0.0
25100115	MULCH, METHOD 2	ACRE	0.5	0.5	0.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50.0	50.0	0.0
28000400	PERIMETER EROSION BARRIER	FOOT	120.0	120.0	0.0
28000500	INLET AND PIPE PROTECTION	EACH	2.0	2.0	0.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	364.0	364.0	0.0
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	280.0	280.0	0.0
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	140.0	140.0	0.0
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	277.0	277.0	0.0
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR(FLEXIBLE)	SQ YD	54.0	54.0	0.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	954.0	954.0	0.0
44000700	APPROACH SLAB REMOVAL	SQ YD	320.0	320.0	0.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	32.0	32.0	0.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	81.0	81.0	0.0
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1.0	1.0	0.0
50102400	CONCRETE REMOVAL	CU YD	19.9	19.9	0.0
50104650	SLOPE WALL REMOVAL	SQ YD	56.0	56.0	0.0
50105220	PIPE CULVERT REMOVAL	FOOT	140.0	140.0	0.0
50200100	STRUCTURE EXCAVATION	CU YD	82.4	82.4	0.0
50300100	FLOOR DRAINS	EACH	12.0	12.0	0.0
50300225	CONCRETE STRUCTURES	CU YD	43	43	0.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	261.8	261.8	0.0
50300260	BRIDGE DECK GROOVING	SQ YD	1,058.0	1,058.0	0.0
50300300	PROTECTIVE COAT	SQ YD	1,287	1,287	0.0
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1.0	1.0	0.0

FILE NAME = c:\projects\d905207 (v8)\70672_text.dgn	USER NAME = collierbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-74 OVER KICKAPOO CREEK - SUMMARY OF QUANTITIES	F.A.I. RTE. 74	SECTION 457-22BR-3	COUNTY MCLEAN	TOTAL SHEETS 42	SHEET NO. 4
PLOT SCALE = 41.5800' / 1" IN.		CHECKED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 70672				
PLOT DATE = 12/21/2007		DATE -				FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				