

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAI 74 **FAI 74**
RURAL **RURAL**
STA. 1035+00
TO 1043+00
90% FED / 10% STATE **90% FED / 10% STATE**
STR# **STR#**
057-0125(EB) **057-0126(WB)**
X071-2A **SFTY-2A**

CONSTRUCTION TYPE CODE:

| CODE NO | ITEM | UNIT | TOTAL QUANTITY | QUANTITY | QUANTITY |
|------------|--|-------|-------------------|----------|----------|
| 50500505 | STUD SHEAR CONNECTORS | EACH | 3,492.0 | 3,492.0 | 0.0 |
| 50606701 | CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1 | L SUM | 1.0 | 0.0 | 1.0 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 63,360 | 63,360 | 0.0 |
| 50800515 | BAR SPLICERS | EACH | 669 | 669 | 0.0 |
| 51100300 | SLOPE WALL 6 INCH | SQ YD | 56.0 | 56.0 | 0.0 |
| 51205200 | TEMPORARY SHEET PILING | SQ FT | 286 | 286 | 0.0 |
| 51500100 | NAME PLATES | EACH | 1.0 | 1.0 | 0.0 |
| 52100010 | ELASTOMERIC BEARING ASSEMBLY, TYPE I | EACH | 12.0 | 12.0 | 0.0 |
| 52100020 | ELASTOMERIC BEARING ASSEMBLY, TYPE II | EACH | 6.0 | 6.0 | 0.0 |
| 52100520 | ANCHOR BOLTS, 1" | EACH | 24.0 | 24.0 | 0.0 |
| 52100540 | ANCHOR BOLTS, 1 1/2" | EACH | 24.0 | 24.0 | 0.0 |
| 54213447 | END SECTIONS 12" | EACH | 1.0 | 1.0 | 0.0 |
| 54244405 | FLUSH INLET BOX FOR MEDIAN, STANDARD 542546 | EACH | 2.0 | 2.0 | 0.0 |
| 542A0223 | PIPE CULVERTS, CLASS A, TYPE 1 18" | FOOT | 140.0 | 140.0 | 0.0 |
| 58700300 | CONCRETE SEALER | SQ FT | 806 | 806 | 0.0 |
| 59100100 | GEOCOMPOSITE WALL DRAIN | SQ YD | 47 | 47 | 0.0 |
| 60100945 | PIPE DRAINS 12" | FOOT | 50.0 | 50.0 | 0.0 |
| 60108100 | PIPE UNDERDRAINS 4" (SPECIAL) | FOOT | 100.0 | 100.0 | 0.0 |
| 60109580 | PIPE UNDERDRAINS FOR STRUCTURES 4" | FOOT | 100 | 100 | 0.0 |
| 60240235 | INLETS, TYPE B, TYPE 5 FRAME, CLOSED LID | EACH | 1.0 | 1.0 | 0.0 |
| 60900240 | TYPE C INLET BOX, STANDARD 609006 | EACH | 2.0 | 2.0 | 0.0 |
| 60900515 | CONCRETE THRUST BLOCKS | EACH | 2.0 | 2.0 | 0.0 |
| * 63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 262.5 | 262.5 | 0.0 |
| * 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 1.0 | 1.0 | 0.0 |
| * 63100169 | TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED | EACH | 1.0 | 1.0 | 0.0 |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 425.0 | 425.0 | 0.0 |
| * 63300205 | REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 200.0 | 200.0 | 0.0 |
| * 63300405 | REMOVAL AND REINSTALLATION OF EXISTING TRAFFIC BARRIER TERMINAL, TYPE 1 | EACH | 1.0 | 1.0 | 0.0 |
| * 63300455 | REMOVAL AND REINSTALLATION OF EXISTING TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 1.0 | 1.0 | 0.0 |
| 64200105 | SHOULDER RUMBLE STRIP | FOOT | 2,073.0 | 1,073.0 | 1,000.0 |

* DENOTES SPECIALITY ITEM

| | | | | | | | | | | |
|--|------------------------|------------|-----------|---|---|---------------------|------------------------|---------------------------|-----------------------|--------------------|
| FILE NAME = c:\projects\d585207 (v8)\78672_text.dgn | USER NAME = collierbw | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | I-74 OVER KICKAPOO CREEK - SUMMARY OF QUANTITIES | F.A.I RTE. 74 | SECTION 057-22)BR-3 | COUNTY MCLEAN | TOTAL SHEETS 42 | SHEET NO. 5 |
| PLOT SCALE = 41.5800' / IN. | PLOT DATE = 12/21/2007 | DRAWN - | REVISED - | | | SCALE: | | SHEET NO. OF SHEETS | | STA. TO STA. |
| | | CHECKED - | REVISED - | | | FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | CONTRACT NO. 70672 |
| | | DATE | REVISED | | | | | | | |