

GENERAL NOTES

G. N. -100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G. N. -442B -- PATCHING SCHEDULES

THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT THE BEST INFORMATION AVAILABLE AT THE TIME OF COMPLETION OF THE PLANS FOR LETTING. VARIATIONS IN LOCATION AND SIZES OF BOTH FULL-DEPTH AND PARTIAL-DEPTH PATCHES MAY OCCUR.

G. N. -780 SPECIAL

PAINT PAVEMENT MARKINGS SHALL BE APPLIED UPON COMPLETION OF THE PATCH WORK. PAINT PAVEMENT MARKINGS SHALL COINCIDE WITH THE EXISTING PAVEMENT MARKINGS. PAINT PAVEMENT MARKINGS SHALL BE LIMITED TO ONLY LENGTH SEGMENTS ASSOCIATED WITH INDIVIDUAL PATCH LOCATIONS AND SHALL NOT BE APPLIED CONTINUOUSLY THROUGH THE PROJECT BETWEEN PATCH LOCATIONS.

ESTIMATED QUANTITIES:

160.0 FOOT CENTERLINE WHITE SKIP DASH - LINE 4"
630.0 FOOT EDGE OF PAVEMENT WHITE SOLID - LINE 4"

NO COMMITMENTS

ADDITIONAL PATCHING NOTES:

PATCH DIMENSIONS SHALL BE IN ACCORDANCE WITH BDE PAVEMENT REHABILITATION METHODS CHAPTER 53 (4.01):

THE MINIMUM CLASS A PATCH DIMENSIONS WILL BE A LENGTH OF 4.5 FT AND A WIDTH THAT INCLUDES HALF THE WIDTH OF THE TRAVEL LANE.

FILE NAME * c:\projects\ad585987 (6)1\70679\sheet.dgn	USER NAME * collarbw	DESIGNED - RTB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - JRP 10-30-07	REVISED -			57	D5 PATCHING 2008-5	DOUGLAS	12	4	
PLOT SCALE * 100.0000 / IN.	CHECKED -	REVISED -	REVISED -			CONTRACT NO, 70679					
PLOT DATE * 12/6/2007	DATE -	REVISED -	REVISED -			SCALE: NA	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		