

SCHEDULE OF QUANTITIES

TABULATION OF CLASS A PAVEMENT PATCH, 10 INCH (SOUTHBOUND)

STATION	LANE	LENGTH (FT)	WIDTH (FT)	TYPE 1	TYPE 2	TYPE 3	TYPE 4	SAWCUTS	TIE BARS	PATCHING REINFORCEMENT
				44200549 (SQ.YD.)	44200553 (SQ.YD.)	44200557 (SQ.YD.)	44200559 (SQ.YD.)	44213200 (FT)	Z0075300 (EACH)	44213000 (SQ.YD.)
1479+98.53	SBDL	6.0	6.0	4.0				36.0		4.0
1477+15.53	SBDL	6.0	12.0		8.0			60.0		8.0
1476+97.53	SBDL	6.0	12.0		8.0			60.0		8.0
1476+64.53	SBDL	6.0	12.0		8.0			60.0		8.0
1447+41.53	SBDL	6.0	6.0	4.0				36.0		4.0
1447+18.53	SBDL	6.0	6.0	4.0				36.0		4.0
1437+86.53	SBDL	20.0	6.0		13.3			64.0	10.0	13.3
1436+16.53	SBDL	12.0	6.0		8.0			48.0		8.0
1435+81.53	SBDL	6.0	6.0	4.0				36.0		4.0
1433+68.53	SBDL	6.0	6.0	4.0				36.0		4.0
1430+11.53	SBDL	6.0	6.0	4.0				36.0		4.0
1427+83.53	SBDL	15.0	12.0			20.0		78.0		20.0
1427+39.53	SBDL	10.0	6.0		6.7			44.0		6.7
1426+43.53	SBDL	6.0	6.0	4.0				36.0		4.0
1417+44.53	SBDL	6.0	6.0	4.0				36.0		4.0
CLASS A PATCH PAGE SUBTOTALS				32.0	52.0	20.0	0.0	702.0	10.0	104.0