

SCHEDULE OF QUANTITIES

TABULATION OF CLASS A PAVEMENT PATCH, 10 INCH (SOUTHBOUND)

STATION	LANE	LENGTH (FT)	WIDTH (FT)	TYPE 1	TYPE 2	TYPE 3	TYPE 4	SAWCUTS	TIE BARS	PATCHING REINFORCEMENT
				44200549 (SQ.YD.)	44200553 (SQ.YD.)	44200557 (SQ.YD.)	44200559 (SQ.YD.)	44213200 (FT)	Z0075300 (EACH)	44213000 (SQ.YD.)
174+68.00	SBDL	6.0	6.0	4.0				36.0		4.0
173+52.00	SBDL	80.0	6.0				53.3	184.0	40.0	53.3
171+24.00	SBDL	6.0	6.0	4.0				36.0		4.0
169+66.00	SBDL	6.0	6.0	4.0				36.0		4.0
167+61.00	SBDL	10.0	6.0		6.7			44.0		6.7
165+75.00	SBDL	6.0	6.0	4.0				36.0		4.0
165+64.00	SBDL	6.0	6.0	4.0				36.0		4.0
165+21.00	SBDL	6.0	6.0	4.0				36.0		4.0
161+83.00	SBDL	6.0	6.0	4.0				36.0		4.0
153+94.00	SBDL	40.0	12.0				53.3	128.0	20.0	53.3
148+96.00	SBDL	6.0	6.0	4.0				36.0		4.0
148+25.00	SBDL	6.0	6.0	4.0				36.0		4.0
142+05.00	SBDL	6.0	6.0	4.0				36.0		4.0
137+44.00	SBDL	6.0	6.0	4.0				36.0		4.0
CLASS A PATCH PAGE SUBTOTALS				44.0	6.7	0.0	106.7	752.0	60.0	157.3