

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	143RS-6	CHRISTIAN	127	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STATION	EXISTING	20800150*	50104400*	50105220*	542C0223	542D0220	542D0223	54207783	54213660*	54213687	54215970	54248515	
		TRENCH BACKFILL	CONCRETE HEADWALL REMOVAL	PIPE CULVERT REMOVAL	PIPE CULVERTS, CLASS C, TYPE 1, 18"	PIPE CULVERTS, CLASS D, TYPE 1, 15"	PIPE CULVERTS, CLASS D, TYPE 1, 18"	PIPE CULVERTS, CLASS D, TYPE 1, 18"	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM, EORS 18"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 15"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	REINFORCED CONCRETE PIPE ELBOW 15"	CONCRETE COLLAR
		CY	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	
99+85	RT												
99+90	30' TO 39' RT			9									
100+00	25' RT +/-												
100+00	24' TO 29' RT												
100+00	25' TO 45' RT			20									
100+00	30' RT												
99+98 TO 100+29	25' RT												
99+98 TO 100+29	30' TO 25' RT												
103+32	26.8' RT										1		
103+65	30' RT +/-			37					1				
103+70	25' TO 35' LT												
103+70	25' TO 35' RT												
103+70	35' LT&RT									2		2	
103+70	25' LT&RT												
107+20	LT	5.7		53		53							
109+00	LT	6.6		59		59							
111+30	LT (COMMON WEALTH AVE.)	7.6		50			50						
146+40	RT	3.6		32		32							
146+80	LT	2.4		17		17							
147+55	LT	1.6		20		20							
147+75	RT	2.4		28		28							
151+90	RT	3.1		27		27							
152+15	LT	1.9		18		18							
153+20	RT	1.7		19		19							
154+20	LT	3.6		26		26							
155+40	LT	2.4		14		14							
155+90	LT	2.1		13		13							
156+40	LT	3.7		33		33							
156+50	RT		1	9		9							
157+25	RT	1.6		18		18							
159+35	RT	12.1		100		100							
160+55	RT	1.4		17		17							
161+40	RT			18		18							
162+05	RT	3.3		24		24							
167+30	LT	AGG. BIT.	3.4	20		20							
298+00	RT	AGG. BIT.	5.8	40	40.0								
305+50	LT			30			30.0						
312+45	RT	AGG.	10.2	98			98.0						
318+75	RT	EARTH		13		13.0							
319+80	RT	BIT.	3.7	30		30.0							
320+00	LT	EARTH		18	2.0	18.0							
320+30	RT	BIT.	4.0	32		32.0							
321+40	RT	AGG.	3.1	26	2.0	26.0							
322+30	RT	AGG.	4.3	20		34.0							
338+50	LT	EARTH		18	2.0	18.0							
345+45	LT	EARTH		17	2.0	17.0							
346+10	RT	AGG.		28		28.0							
358+50	RT	EARTH		25	2.0	25.0							
358+50	LT	BIT.	3.1	24			35.0						
371+75	RT	EARTH		23	2.0	23.0							
		TOTAL	104.4	17.0	1122.5	40.0	829.0	163.0	50.0	1.0	2.0	1.0	2.0

* SEE STRUCTURE SCHEDULES FOR ADDITIONAL QUANTITIES.

PLOT DATE = Dec-12-2007 10:35:28AM
 FILE NAME = c:\projects\ed53581\hatch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. / HORIZ.
 DATE

DRAWN BY
 CHECKED BY