

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	143RS-6	CHRISTIAN	127	17
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

20200100 EARTH EXCAVATION\*  
20400800 FURNISHED EXCAVATION\*

LI									RI								
STATION	LENGTH	CUT @ STATION	AVG END AREA	EARTH EXCAVATION	ADJUSTED	FILL @ STATION	FILL REQUIRED	BALANCE	STATION	LENGTH	CUT @ STATION	AVG END AREA	EARTH EXCAVATION	ADJUSTED	FILL @ STATION	FILL REQUIRED	BALANCE
	FT	SF	SY	CY	25% SHRINKAGE	SF	CY	WASTE (+) SHORTAGE (-)		FT	SF	SY	CY	25% SHRINKAGE	SF	CY	WASTE (+) SHORTAGE (-)
348+00		0			0.00	0	1.30	-1.30	348+00	50	0	0.000	0.00	0.00	0.0	0.56	-0.56
348+50	50	0	0.000	0.00	0.00	1.4	2.96	-2.96	348+50	50	0	0.000	0.00	0.00	0.6	1.85	-1.85
349+00	50	0	0.000	0.00	0.00	1.8	4.07	-4.07	349+00	50	0	0.000	0.00	0.00	1.4	3.33	-3.33
349+50	50	0	0.000	0.00	0.00	2.6	5.65	-5.65	349+50	50	0	0.000	0.00	0.00	2.2	4.81	-4.81
350+00	50	0	0.000	0.00	0.00	3.5	7.69	-7.69	350+00	50	0	0.000	0.00	0.00	3	6.57	-6.57
350+50	50	0	0.000	0.00	0.00	4.8	8.61	-8.61	350+50	50	0	0.000	0.00	0.00	4.1	9.07	-9.07
351+00	50	0	0.000	0.00	0.00	4.5	9.26	-9.26	351+00	50	0	0.000	0.00	0.00	5.7	11.02	-11.02
351+50	50	0	0.000	0.00	0.00	5.5	11.11	-11.11	351+50	50	0	0.000	0.00	0.00	6.2	11.85	-11.85
352+00	50	0	0.000	0.00	0.00	6.5	12.41	-12.41	352+00	50	0	0.000	0.00	0.00	6.6	13.06	-13.06
352+50	50	0	0.000	0.00	0.00	6.9	13.33	-13.33	352+50	50	0	0.000	0.00	0.00	7.5	14.91	-14.91
353+00	50	0	0.000	0.00	0.00	7.5	15.93	-15.93	353+00	50	0	0.000	0.00	0.00	8.6	20.28	-20.28
353+50	50	0	0.000	0.00	0.00	9.7	26.20	-26.20	353+50	50	0	0.000	0.00	0.00	13.3	30.74	-30.74
354+00	50	2	0.111	1.85	1.39	18.6	35.28	-33.89	354+00	50	0.7	0.039	0.65	0.49	19.9	46.85	-46.37
354+50	50	1.3	0.072	1.20	0.90	19.5	32.78	-31.88	354+50	50	8.3	0.461	7.69	5.76	30.7	44.44	-38.68
355+00	50	0.5	0.028	0.46	0.35	15.9	22.41	-22.06	355+00	50	0.8	0.044	0.74	0.56	17.3	22.69	-22.13
355+50	50	0	0.000	0.00	0.00	8.3	10.46	-10.46	355+50	50	0	0.000	0.00	0.00	7.2	8.80	-8.80
356+00	50	0	0.000	0.00	0.00	3.0	3.80	-3.80	356+00	50	0	0.000	0.00	0.00	2.3	2.78	-2.78
356+50	50	0	0.000	0.00	0.00	1.1	1.11	-1.11	356+50	50	0	0.000	0.00	0.00	0.7	0.74	-0.74
357+00	50	0	0.000	0.00	0.00	0.1	0.09	-0.09	357+00	50	0	0.000	0.00	0.00	0.1	0.09	-0.09
357+50	50	0	0.000	0.00	0.00	0.0	0.00	0.00	357+50	50	0	0.000	0.00	0.00	0.0	0.00	0.00
358+00	38	0	0.000	0.00	0.00	0.0	0.00	0.00	358+00	50	0	0.000	0.00	0.00	0.0	1.20	-1.20
358+38									358+50	50	0	0.000	0.00	0.00	1.3	5.09	-5.09
358+69									359+00	50	0	0.000	0.00	0.00	4.2	8.24	-8.24
359+00	31	0	0.000	0.00	0.00	4.3	0.08	-0.08	359+50	50	0	0.000	0.00	0.00	4.7	8.98	-8.98
359+50	50	0	0.000	0.00	0.00	5.5	0.10	-0.10	360+00	50	3.4	0.189	3.15	2.36	5.0	7.13	-4.77
360+00	50	0	0.000	0.00	0.00	7.1	0.13	-0.13	360+50	50	8.4	0.467	7.78	5.83	2.7	3.15	2.69
360+50	50	0	0.000	0.00	0.00	3.6	0.07	-0.07	361+00	50	0	0.000	0.00	0.00	0.7	0.65	-0.65
361+00	50	0	0.000	0.00	0.00	1.6	0.03	-0.03	361+50	50	0	0.000	0.00	0.00	0.0	0.00	0.00
361+50	50	0	0.000	0.00	0.00	1.0	0.02	-0.02	362+00	50	0	0.000	0.00	0.00	0.0	0.00	0.00
362+00	50	0	0.000	0.00	0.00	0.0											
TOTAL				3.5			227.3	-224.7	TOTAL				20.0			288.9	-273.9

\*SEE STRUCTURE SCHEDULES FOR ADDITIONAL QUANTITIES.

\*SEE STRUCTURE SCHEDULES FOR ADDITIONAL QUANTITIES.

PLOT DATE = Dec-12-2007 10:35:29AM  
FILE NAME = c:\projects\ed53581\hntsch.dgn  
PLOT SCALE = 1/8"=1'-0"  
USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

# SCHEDULES

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY