

CONTRACT NO. 72943

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	11RS-8	ADAMS	64	19
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 7810 & 7825 (IL 96)				

## SCHEDULE OF QUANTITIES

### STONE RIPRAP, CLASS A4

LOCATION	QUANTITY ( SQ YD)
F. A. P. 7810 ( IL 96)	
STA. 2324+85.00 RT	115.18
<b>PROJECT TOTAL</b>	<b>115</b>

### FILTER FABRIC

LOCATION	QUANTITY ( SQ YD)
F. A. P. 7810 ( IL 96)	
STA. 2324+85.00 RT	115.18
<b>PROJECT TOTAL</b>	<b>115</b>

### COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

LOCATION	QUANTITY ( FOOT)
F. A. U. 7810 ( IL 96)	
STA. 2339+66.50 to STA. 2340+16.30 LT	49.80
<b>PROJECT TOTAL</b>	<b>50</b>

### CLASS SI CONCRETE (OUTLET)

LOCATION	QUANTITY ( CU YD)
F. A. U. 7810 ( IL 96)	
STA. 2340+10.00 to STA. 2340+46.00 LT	3
<b>PROJECT TOTAL</b>	<b>3</b>

### EARTH EXCAVATION

LOCATION	QUANTITY ( CU YD)
F. A. U. 7810 ( IL 96) ( MANHOLE INSTALLATION)	
STA. 2312+30.37, 18.58' RT	
FILL = 20.17	
( PIPE CULVERT EXTENSION)	
STA. 2324+85.00 RT	
CUT =	4.55
FILL = 22.64	
( CONCR. GUTTER TYPE A IMPROVEMENT)	
STA. 2338+49.70 to STA. 2340+16.30 LT	
CUT =	28.97
FILL = 4.94	
<b>PROJECT TOTAL</b>	<b>34</b>

### EARTH EXCAVATION ( WIDENING)

LOCATION	QUANTITY ( CU YD)
F. A. U. 7810 ( IL 96) ( FOR HMA SHOULDERS, 8")	
STA. 2342+80.00 to STA. 2343+80.00 RT	6.17
STA. 2343+80.00 to STA. 2345+34.20 RT	14.28
STA. 2344+41.00 to STA. 2345+34.20 LT	8.63
BRIDGE OMISSION ( S. N. 001-0033) STA. 2345+64.20 to 2345+96.20	
STA. 2346+26.20 to STA. 2347+40.00 RT	10.54
STA. 2346+36.00 to STA. 2347+40.00 LT	9.63
STA. 2347+40.00 to STA. 2348+40.00	12.35
<b>PROJECT TOTAL</b>	<b>62</b>

### FURNISHED EXCAVATION

LOCATION	QUANTITY ( CU YD)
F. A. P. 7810 ( IL 96)	
For FILL Quantity Breakdown	
See EARTH EXCAVATION	
FILL = 47.76 CU YD x 1.28	61.13
EARTH EXCAVATION	-33.52
<b>PROJECT TOTAL</b>	<b>28</b>

### GRADING AND SHAPING SHOULDERS

LOCATION	QUANTITY ( UNIT)
F. A. U. 7810 ( IL 96)	
STA. 2342+80.00 to STA. 2345+34.20 RT	254.20
STA. 2344+41.00 to STA. 2345+34.20 LT	93.20
BRIDGE OMISSION ( S. N. 001-0033) STA. 2345+64.20 to STA. 2345+96.20	
STA. 2346+26.00 to STA. 2348+40.00 RT	213.80
STA. 2346+36.00 to STA. 2348+40.00 LT	204.00
<b>SUBTOTAL ( In FT)</b>	<b>765</b>
( 1 UNIT = 100' )	
<b>PROJECT TOTAL</b>	<b>7.7</b>

### LEGEND

( # ) QUANTITY DESIGNATED FOR CITY OF QUINCY  
[ # ] QUANTITY DESIGNATED FOR ADAMS COUNTY

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
F.A.U. Route 7810 & 7825 (IL 96)  
Section 11RS-8  
ADAMS COUNTY

SCALE: VERT.  
HORIZ.  
DATE: NOVEMBER 28, 2006

DRAWN BY: JWC  
CHECKED BY: RSC

PLOT DATE = Nov-28-2007 08:44:56PM  
 FILE NAME = c:\projects\650605\shsch.dgn  
 PLOT SCALE = 1/8"=1'-0" / IN.  
 USER NAME = laughlin-1