

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE SFTY-4A	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	058-0066	058-0067	058-0076
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SO YD	102		102	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	66			66
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	778			778
44004250	PAVED SHOULDER REMOVAL	SO YD	102		102	
50102400	CONCRETE REMOVAL	CU YD	52.3	24.6	27.7	
50157300	PROTECTIVE SHIELD	SO YD	300			300
50300255	CONCRETE SUPERSTRUCTURE	CU YD	52.3	24.6	27.7	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7920	3500	4420	
50800515	BAR SPLICERS	EACH	62	28	34	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	294	154	140	
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.50
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1		1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CALDA	4	2	2	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1			1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15650	7380	8270	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2567	1218	1349	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	825	350	475	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	825	350	475	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1057			1057
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1206	466	740	
78300500	PAVEMENT MARKING REMOVAL	SO FT	358	114	244	
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	13	13		
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	162	46	87	29
X7010820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	L SUM	1	0.5	0.5	
X7012615	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	EACH	3	1	1	1
XX005494	WATERPROOFING MEMBRANE SYSTEM (SPECIAL)	SO YD	778			778
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO YD	9			9
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	35			35
Z0016200	DECK SLAB REPAIR (PARTIAL)	SO YD	108			108
Z0021400	EXPANSION JOINT (SPECIAL)	FOOT	60			60
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1	
* 78100300	REPLACEMENT REFLECTOR	EACH	13	13		

* SPECIALTY ITEMS

Rev.

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - ---	REVISED - ---			72	DT BRIDGE REPAIRS 2008-2	MACON	31	3
		CHECKED - ---	REVISED - ---			SCALE: 20_____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 74270		
		DATE - -----	REVISED - ---			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				