

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1832	5BR-2	WASHINGTON	97	55
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

RESURFACING SCHEDULE

STATION	RT/LT	HOT-MIX ASPHALT BS WIDENING 9" (SQ YD)	AGGREGATE PRIME COAT (TON)	BIT. MAT'L PRIME COAT (TON)	HMA CONC BINDER SUPER, MIX "B" (TON)	HMA CONC SURF CSE, SUPER, MIX "C", N70 (TON)	SUB-BASE GRANULAR MATERIAL TY-A 12" (SQ YD)	HMA SHOULDERS 8" (SQ YD)	AGG. SHLD TYPE B 6" (SQ YD)
1508+00.00 TO 1508+90.00	RT/LT				10.08				
1507+75.00 TO 1510+52.50	RT								
1507+75.00 TO 1510+68.30	LT	97.77							
1508+00.00 TO 1510+86.00	RT/LT		1.14	0.24		64.06		190.67	190.67
1508+90.00 TO 1510+86.00	RT/LT				307.33				
1510+67.40 TO 1510+84.00	RT/LT						50.56		
1511+18.90 TO 1514+25.00	LT	102.03							
1511+16.00 TO 1513+15.00	RT/LT				312.03				
1511+09.00 TO 1514+25.00	RT								
1511+16.00 TO 1514+25.00	RT/LT		1.24	0.26		69.22		206.00	206.00
1513+15.00 TO 1514+25.00	RT/LT				12.32				
TOTAL		199.80	2.38	0.50	641.76	133.28	50.56	396.67	396.67

GUARDRAIL SCHEDULE

STATION	RT/LT	SPBGR (FT)	TBT - T1 (SPECIAL) (EA)	TBT - T6A (EA)	GUARDRAIL MRKS TY-A (EA)	BI-DIREC PRISM BARR REFLEC (EA)
1508+45.25 TO 1510+76.50	RT	137.5	1	1	3	
1509+45.25 TO 1510+89.00	LT	50	1	1	2	
1510+86.00 TO 1511+16.00	RT/LT					2
1511+22.25 TO 1513+53.50	LT	137.5	1	1	3	
1511+11.00 TO 1512+54.75	RT	50	1	1	2	
TOTAL		375	4	4	9	2

PAVEMENT MARKING SCHEDULE

STATION		PAVEMENT - THERMOPLASTIC				
		4" WHITE LINE (FT)	4" YELLOW LINE (FT)	YELLOW SKIP DASH LINE 4" (FT)	DBL AMBER RSD REFL PKM (EA)	24" WHITE LINE (FT)
1504+69.00 TO 1517+36.00	CL			316.75	16	
1504+69.00 TO 1517+36.00	RT/LT	2414				
1507+51.24 TO 1513+00.00	RT		400.0			38
1509+00.00 TO 1513+00.00	CL			316.75	16	
SUB-TOTAL		2414	400.00	316.75	16	
TOTAL			3130.75		16	38

TEMPORARY PAVEMENT MARKING SCHEDULE

STATION		PAVEMENT MARKING			WORK ZONE PVMT REMOVAL (SQ FT)	PVMT MRKG REMOVAL (SQ FT)
		LINE 4" PAVEMENT (FT)	LINE 6" (TEMP. BARR.) (FT)	LINE 24" PAVEMENT (FT)		
1504+95.00	RT STOP BAR			12	24.0	
1504+70.00	LT STOP BAR			12	24.0	
1504+70.00	1517+35.00 STAGE 2		2530		843.3	
1504+95.00 TO 1517+35.00	STAGE 1	2480			826.7	
1504+70.00 TO 1517+35.00	RT/LT					843.3
1504+70.00 TO 1517+35.00	CL					105.4
1507+95.00 TO 1515+64.50	STAGE 1		770			
1506+40.50 TO 1515+69.50	STAGE 2		930			
1507+51.24	MALLARD RT			46	92.0	
1517+35.00	LT STOP BARS			24	48.0	
SUB-TOTAL						
TOTAL		5010	1700	94	1858.0	948.7

S.N. 095-0078

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES FAS ROUTE 1832 SECTION 5BR-2 WASHINGTON COUNTY
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY