

STAGE CONSTRUCTION SCHEDULE

LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE)	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE)
	FOOT	FOOT	EACH	EACH
NB STAGE I	475		1	
NB STAGE II		475		1
SB STAGE I	475		1	
SB STAGE II		425		1
TOTALS	950	900	2	2

SHOULDER SCHEDULE

LOCATION	LT OR RT	HMA SURFACE REMOVAL, 1"	HMA BINDER USE, 1" (LL-19.0, N90)	INLETS TO BE ADJUSTED
		SQ YD	TONS	EACH
NORTHBOUND				
STA 1471+50 TO STA 1477+55	RT	672.2	94.1	1
STA 1481+59 TO STA 1488+50	RT	767.8	107.5	1
STA 1471+50 TO STA 1477+20	LT	633.3	88.7	1
STA 1481+25 TO STA 1488+50	LT	805.6	112.8	
SOUTHBOUND				
STA 1473+50 TO STA 1476+50	RT	333.3	46.7	1
STA 1480+54 TO STA 1489+75	RT	1023.2	143.2	1
STA 1473+50 TO STA 1476+84	LT	371.1	52.0	1
STA 1480+88 TO STA 1489+75	LT	985.5	138.0	1
TOTALS		5592.0	783.0	7

TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION	TEMPORARY PAVEMENT MARKING - LINE 4"		TEMPORARY PAINT PAVEMENT MARKING - LINE 6"		SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER
	WHITE	YELLOW	WHITE	YELLOW			
	FT	FT	FT	FT			
NB STAGE I	3202	3124		475		2108.6	32
SB STAGE I	2952	3259	475			2070.2	31
NB STAGE II	4738	1602		475	90.9	2113.2	32
SB STAGE II	4466	1450	425		90.9	1972.0	29
NB					509.9		
SB					453.3		
SUB-TOTAL	15358	9435	900	950			
TOTALS	24,793		1850		1145	8264	124

PERMANENT PAVEMENT MARKING SCHEDULE

LOCATION	PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	REPLACEMENT REFLECTOR (CRYSTAL)
		SQ FT	FT	EACH
NORTHBOUND				
STA 1454+95 TO STA 1464+95	166.7	500	50	50
STA 1471+95 TO STA 1487+95	1333.4	4000	80	80
SOUTHBOUND				
STA 1473+83 TO STA 1488+33	1208.3	3625	73	73
STA 1488+33 TO STA 1489+33	41.7	125	3	3
STA 1495+33 TO STA 1496+33	8.3	25	3	3
STA 1496+33 TO STA 1502+00	94.5	283.6	28	28
STA 1502+00 TO STA 1506+33	36.1	108.4	11	11
TOTALS	2889	8667	248	248

FILE NAME =	USER NAME = harbaughrd	DESIGNED -	REVISED -
c:\projects\ed06306\plan\pin06306a.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/20/2007	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: NA SHEET NO. 4 OF 42 SHEETS STA. TO STA.

Rev. 2-14-08

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
255	60-8B-II	MADISON	42	4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76A25	